NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/17-18/0090 **Date : 10-01-2018**

Sintex Industries Ltd - Yarn Division
Kalasagar, Sattadhar, Ahmedabad
Gujrat

Kind Attn : Mr. Shashank Jain
Email : shashank.jain@sintex.co.in
Contact No : 7307583088

Subject : Quotation for Telescopic Conveyor

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr.No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Telescopic Conveyor Make - NIHVA (HSN CODE : 84289090)**				
Technical Specifications	• Length of Conveyor : 16 meter • Extended Length of Conveyor : 10 meter • Fixed Length of Conveyor : 6 meter • Width of Conveyor : 1 meter • Material to be handle : Cartons/ Bags/Boxes • Weight of Material : 50 kg/each approx. • Size Of Cartons :645LX435WX507H & 750LX375WX507H • Material of Construction : MS Painted • Loading Height From Shop Level : 1400 mm • Speed Of Conveyor : 30 mtr/min Max. • Temperature : Ambient • Drive Motor : 5 HP Coupled Geared Motor • Control Operation : PLC, Sensor and Control Panel • Adjustable up/down in loading & unloading by: Hydraulic	1	No	17,00,000	17,00,000
B	**Installation ,Comissioning & Training Charges**	1	No	10,000	10,000

GST PUNE:	**27AAECN0437H1ZM**
GST GUJRAT:	**24AAECN0437H1ZS**

Amount in Words	**Total Amount**	**17,10,000**
	Rupees Seventeen Lacs Ten Thousand Only	

Image Attached For your Reference



Click Here for Operational Video: https://youtu.be/4aWtD0hqO9M

Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
3 Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel.

Client Scope

1 Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2 All structure support is in client scope
3 NIHVA Will provided structure drawing only if required
4 Existing Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	3% Extra
3	**Freight Notes**	:	Extra as applicable
4	**Delivery**	:	8-9 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% advance along with confirm Purchase Order & balance before dispatch
6	**Insurance**	:	Extra if applicable
7	**Tax**	:	GST : Extra as applicable at the time of delivery
8	**Validity**	:	Validity of Offer is 15 days from the of quotation
9	**Warranty**	:	12 Months from the date of supply

Please feel free to Contact **Mr. Mayur Derle** on **7709209333** For any further Clarification /Information in this Concern.

With Best Regards

Pooja Badre
7709586333
For Nihva Technologies Pvt Ltd