Sales Quotation

Quotation No - SQT/19-20/1778 **Date : 02.07.2019**

Finearc Systems Pvt. Ltd
21, F-2 Block, MIDC, Pimpri
Pune - 411018
Maharashtra, India

Kind Attn: **Mr. Hegde**
Email: rhegde@finearcsystems.com
Contact No: 9763720513

Project Name And Location :

Subject : Quotation for Machine Protection Door RP300 - High Sea Sale
Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr. No	Description	Window	Curtain	Controller	Qty	Unit	Rate In INR (High Sea Sale)	Net Amount INR
A	**Albany Make Rapid Roll Up Door RP300**							
Door version:	Vertical Rapid Roller Door for machine protection.							
Side Frames:	Aluminum anodized two parts, to have easy access to switches and service.							
Bottom beam:	Aluminium anodized.							
Drive unit:	Drive unit IP 55, either RH or LH as an option, with control cable (standard length = height of door)							
Power suppy:	3/(N)/PE 230/380/400/415 V, 50 Hz							
Safety features:	Safety edge with cable chain integrated in side frames, door line photocell (Transmitter / Receiver) inside side frames, emergency crank and mechanical drop-down protection.							
1	**Size: 1850 mm (W) X 2460 mm (H)** **(Supply)**	**700 mm (W) X 500 mm (H)**	**Rolltex Orignal**	**MCC**	**2**	No	545,000	1,090,000
	Total				**2**	No		**1,090,000**

GST Pune	27AAECN0437H1ZM

Total Price	**1,090,000**

Note:

1. Above prices are excluding all other structural members required for installation of the door and Taxes.
2. Complete structural design, build are in client scope.
3. **Above prices are CIF prices by Sea which are without any Custom duty, Custom Clearance, Local Transport**
4. There will be High Sea Sales agreement between NIHVA and Finearc Systems Pvt. Ltd and this is to signed by both parties before arrival of equipment at Seaport.
5. Since this is Sea consignment both the parties will have to take at most care during this transaction as the agreement is required to discharge in between the period of dispatch and receipt at sea port
6. For any reason if consignment gets hold at custom NIHVA will not be responsible for any delayed charged or penalty.

Client Scope of Work:

1. Custom Duty + Custom Clearance + Local Transport, till site in clients Scope. NIHVA will handover BL to client for further all process & action till material reaches at site & unloads at required place.
2. For High Sea sale responsibility of NIHVA ceases on transfer of BL to client.
3. Client should issue required forms to NIHVA for all Tax Exemptions.

General Prerequisites Required at Site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places.
3 Provide electrical cables near to the installation machinery
4 Fork lift/crane to be provided if required .
5 Scaffolding require for Installation it is in client scope.

Limit of Supply

1 Provide place to store the material to be installed .
2 Be responsible for the safe custody of all material.
3 Provide place to safely store all the tools of installation
4 Provide change & rest room for the workers.

Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
2 In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3 Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel.

Client Scope

1 Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2 Any civil / masonry/structural work required to support are in client scope
3 All structure support is in client scope
4 NIHVA Will provided structure drawing only if required
5 Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	CIF, Navha Sheva, Mumbai Sea Port
2	**P & F Charges**	:	@3% of total supply value
3	**Delivery**	:	11 - 12 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval
4	**Frieght Notes**	:	Extra as applicable
5	**Payment**	:	80% Advance along with order & 20% before dispatch.
6	**Validity**	:	Validity of Offer is 15 days from the date of quotation
7	**Warranty**	:	12 months from the date of supply

Please feel free to Contact **Mr. Arjun Patil** on **8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd