BN ENTERPRISES
TOTAL PACKAGING SOLUTION
THE COMPLETE CONTROL PANEL SOLUTION

Manufacturer of
All types of Industrial Conveyors, Shrink Wrapping Machines, Lable Applicaters, Special Purpose Machines, Control Panels & Automation



Factory: Gate No.20 ARVI Village Near Khedshivapur Industrial Estate Tal Haveli Pune-412205.

Quotation

Ref No: BN/20528/2021 – 2022 **Date: 06.01.2022**

GST NO-27ANGPC6263Q1ZI

To,

Nihva Technologies Pvt Ltd.

Add: 187,G Block, 1st Floor, Above Renault Show Room, MIDC, Chinchwad, Pune- 411 019
Mob: 9730020333, 9168940333.
Email: purchase@nihva.com , procurement@nihva.com .
Kind Attn: Mr. Pranav Marne Sir.

Sub: Offer for Automatic Cartoning Machine Model No: BNE Economic

Dear Sir,

This is with refers to your telecom held with our Mr. Choure Sir regarding your requirement for **Automatic Cartoning Machine Model No: BNE Economic**We are submitting herewith our techno commercial Offer for your perusal. Ours is an ISO 9001 - 2015 certified company. Our valued clients include Mahindra and Mahindra Limited, Coca Cola, Tirumalla Oil Refinery Pvt. Ltd., Century Enka Limited, Savera Auto Comps Pvt. Ltd., Candigra Vision Process Equipments Pvt. Ltd., Eton Industrial Systems Pvt. Ltd., Garaware Ropes Limited, Talbros Automative Components Limited, Bakelite Food Processing Equipments Pvt. Ltd., Fulham India Pvt. Ltd., Feather feel Nonwoven Pvt. Ltd., Woodward India Pvt. Ltd., Fluid Controls Pvt. Ltd., Brainbees Solution Pvt.Ltd. Retier India Pvt. Ltd. Inoxpa India Pvt. Ltd. etc.

We hope you will find the offer in line of your requirement. If you need any further techno commercial clarifications please feel free to contact us.

Waiting for your favorable reply at earliest, Assuring for the best and personal attention at all times

With Best regards,



Choure B.
Cell: +91-8308746511, +91-8308773422Tel: 020 65232148
Email: inf.bnenterprises@gmail.com / sales@bnenterprises.net

BN ENTERPRISES
TOTAL PACKAGING SOLUTION
THE COMPLETE CONTROL PANEL SOLUTION

Manufacturer of
All types of Industrial Conveyors, Shrink Wrapping Machines, Lable Applicaters, Special Purpose Machines, Control Panels & Automation



Factory: Gate No.20 ARVI Village Near Khedshivapur Industrial Estate Tal Haveli Pune-412205.

Automatic Cartoning Machine Model No: BNE Economic





Factory: Gate No.20 ARVI Village Near Khedshivapur Industrial Estate Tal Haveli Pune-412205.

Sr. No.	Particular Description
A	Continuous Motion cartonator OMEGA 120 Consisting of:
01	Adjustable Carton Magazine for Stucking cartons which are opened by suction by vaccume pump of 500LPM
02	In-feed product conveyor consisting of partition (Pockets) which are adjustable to Carton Size.
03	In-feed product conveyor consisting of partition (Pockets) which are adjustable to Carton Size.
04	Carton Length adjustment system.
05	Continuous motion landing stations for inserting product by push rods which moves simultaneously with the carton chain.
06	Tuck-in mechanism for tucking the flaps and closing the flaps.
07	Mitsubishi make PLC system comprising of check Devices as below: NO Product - NO CARTON NO CARTON- NO PUSHER Low level carton indication system Stoppage system when in EMERGENCY Touch Screen Operating Panel.
08	Product Feeding is Manual



Factory: Gate No.20 ARVI Village Near Khedshivapur Industrial Estate Tal Haveli Pune-412205.

Make of Components:

Material of Construction	SS 304(only For Contact Parts)-MS Powder Coated
Conveyor- Drive Motor	AC MOTOR (MMC MAKE)
On/Off Switch	SIEMENS SALZER
Contactors /MCB	SIEMENS ABB, L&T OR ANY EQUIVALENT
Cables	POLYCAB
S. S. Sheet Thickness - 304	2 mm
PLC	MITSUBISHI
HMI	MITSUBISHI
SERVO MOTOR WITH SERVO DRIVE	MITSUBISHI
GAP SENSOR	LEUZE
SMPS INPUT 230 V AC OUTPUT 240V AC	OMARON
CABLE TRAY	TRINITY
Product Sensors	LEUZE

Output Speed: 40-60 Boxes per minute

PRICING STRUCTURE OF EQUIPMENT:

Sr. No.	Machine Name / Model	Qty.	Price in INR
1.	**Automatic Cartoning Machine** **Model No: BNE Economic** **Output Speed: 40-60 Boxes per minute**	01	34,00,000.00



Factory: Gate No.20 ARVI Village Near Khedshivapur Industrial Estate Tal Haveli Pune-412205.

Terms and Conditions:

Price Basis	The above prices are Ex Works, exclusive of all applicable taxes & duties.
Payment Terms	50 % advance payment along with the purchase order. 50 % balance payment against Performa Invoice before dispatch.
Delivery	90days to130 days from the date of receipt of confirmed purchase order or from the date of receipt of the advance payment or from the date of receipt of the samples whichever is later.
Mode of Transport	BY Road, Freight – "TO PAY" Basis.
Taxes	18% extra GST
Packing	4 % for Box packing.
Insurance	To be borne by customer OR Covered by B.N.ENTERPRISES @ 0.50% on the basic value.
Inspection	At our works before dispatch at your cost.
Manual	Machine instruction manual will be supplied free of cost.
Jurisdiction	In case of any dispute/s all the claims are subjects to Pune Jurisdiction only.
Cancellation	Once we confirm the technically & commercially clear order, we will take up the manufacture of the machine immediately in hand. Hence, we cannot accept any changes or cancellation of order and thus we cannot refund your advance amount back to you. The placing of an order with us implies acceptance of the conditions of sale here in stated regardless of any constricting clauses in the Buyers purchase order.
Warranty	We provide warranty of 12 months from the date of dispatch against manufacturing defects Or default workmanship. Warranty does not cover any electric or electronic parts such as AC variable drive, motor, PLC, sensor, relay etc.
Special Note	If the machine is not picked up after the final inspection (Beyond the delivery time) by you then we will charge 1.5% per week for the basic value of the machine and it has to be cleared before the Machine dispatch.
Validity	30 days from the date of quotation.

Important Installation Commissioning Terms And Conditions:

Inspection & Training	FAT at our works before dispatch. It is COMPULSORY that your technician is trained at our works for three days prior to dispatch of the machinery. A skilled technician is necessary for the same. We shall provide all the necessary training regarding the working/maintenance of the machine, the training charges will be free but the lodging and boarding and conveyance etc of our technician will be borne by you. If your operator is not trained we are not responsible for the satisfactory working of the machine.
Installation& Commissioning	The cost of installation and commissioning will be Rs. 5,000/- per person, per day plus to and fro charges for the visit. Before the visit of the technician, please ensure that all civil and ancillary works are completed. Samples of bottles, caps, label rolls should be available in sufficient quantity. In case the above is not ready during the visit of our technician, they will go back, and RE-VISIT charges will be to your account. Customer has to provide the required samples (bottles, caps, Ampoule, Label etc) required in the trial of the machine at his cost. Quantity of the samples will be mentioned prior to the trial. Please make sure the trail Samples are arranged in advance so this may not delay the delivery time. Or the delivery time scheduled in the quotation will not be valid.

Any addition other than the basic/standard machine details mention in the quotation will cost extra. This quotation cancels all the previous given quotation. Note: As per the Company rules the Company have right to change the specification/design for the better functioning of the machine.