NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Ratilal Bhagwandas Construction Co Pvt.
Pune, India

Date : 12.10.2019
Quote NO : SQT/19-20/2146R
Kind Attn : Ashwini Udge.
Email Id : ashwini.udge@ratilal.in
Contact No: 9850976739

Subject : Quotation for Rolling Shutter, High Speed Door, fire Rated Rolling Shutter, Sectional Door .(Project - Araymond Fastners India Pvt Ltd, Chakan.)

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	GI Motorized Rolling Shutter	5000	7000	1	233,000	233,000	20,000	20,000
2	GI Motorized Rolling Shutter	3000	3000	3	86,000	258,000	20,000	60,000
3	GI Motorized Rolling Shutter	5000	3000	2	118,000	236,000	20,000	40,000
4	Albany Make Rapid Roll Up Door RR300+ALU	2400	3000	4	593,000	2,372,000	20,000	80,000
5	Albany Make Rapid Roll Up Door RR300+ALU	1800	3000	2	580,000	1,160,000	20,000	40,000
			Total			**4,259,000**		**240,000**
6	P&F Charges			3%		127,770		
	Total Without Taxes					4,386,770		240,000
	GST Extra @ 18%			18%		789,618.60		43,200
	Total With Taxes					**5,176,389**		**283,200**
7	Transportation Charges					In Client Scope		
8	Unloading Charges @ Site					In Client Scope		
	Optional Accessories							
9	Additional Operating Switch			1	6,500	6,500		
10	Remote control			1	5,000	5,000		
11	Safety Photocell			1	8,500	8,500		
12	Flashing Light			1	12,500	12,500		
13	Interlocking			1	18,000	18,000		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorized Rolling Shutter

Sr .No.	Specification	GI Motorized Rolling Shutter
1	Description:	Motorised Rolling Shutter with GI Laths with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete /Steel & Side
4	Curtain Panel	The panel made of 1.0mm thick MS.
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	Hood Cover	Made of GI Sheet Thickness 1.2 mm GF mm with 25x25x3mm angle stiffener
12	Surface finish	PU paint or Powder coated
13	Drive Unit & Mounting Type	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

RR300+AL

Sr .No.	Specification	ASSA ABLOY (Albany) Rapid Roll Up Door RR300+AL
1	Door panel	Motorised Rolling Shutter with MS Laths with thickness of 1 mm.
2	Mounting Location area	Aluminium, anodized with shafts made of galvanized steel
3	Wind Reinforcement	Door Panel wind tabs for improved wind resistance
4	Vision Window	Vertical Transparent Vision panel
5	Side Frames	Aluminium profiles, anodised
6	Drive Unit	Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)
7	Self-opening	Standard - the door can be opened partially up to 1,8 m by releasing the brake manually.
8	Bottom beam	Anodized extruded aluminium.
9	Control system	MCC Vector Control - frequency converter control system for a dynamic, smooth door movement, located close to the drive unit Max. Opening Speed 2.2m/s Max. Closing Speed 0.9 m/s
10	Safety features	Safety edge, safety photocell (Transmitter/Receiver) inside side columns.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd