NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Ashok Construction
B-601, Sukhwani Glory
Dapodi, Pune- 411012

Date : 3.11.2020
Quote NO : SQT.20.21.2803R1
Kind Attn : Ashok Pilgonde
Email Id : ashokpilgonde@gmail.com
Contact No: 9552567922

Project, Location : Isnapur, Hyderabad

Subject : Quotation for Sliding Glass Door and Gear Operated Single Skin Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Sliding Glass Doors**	2000	2500	1	230,000	230,000	20,000	20,000
2	**Gear Operated Single Skin Rolling Shutter**	5000	5000	1	147,000	147,000	20,000	20,000
3	**Gear Operated Single Skin Rolling Shutter**	4000	5000	1	122,000	122,000	20,000	20,000
4	**Gear Operated Single Skin Rolling Shutter**	2500	3500	1	66,000	66,000	20,000	20,000
5	**Gear Operated Single Skin Rolling Shutter**	2500	3000	1	60,000	60,000	20,000	20,000
	Total			**5**		**625,000**		**100,000**
6	P&F Charges			3%		18,750		
	Total Without Taxes					643,750		100,000
	GST Extra @ 18%			18%		115,875.00		18,000
	Total With Taxes					**759,625**		**118,000**
7	Transportation Charges					Extra at atcual		
8	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification



Automatic Sliding Glass Door

Sr .No.	Specification	Sliding Glass Door
1	Operator Type	Bi part operator.
2	User Modes	Auto, Open, In,Out, Locked, Partial opening
3	Operator Dimension	125 x 168 mm
4	Installer Settings	Opening speed, Closing Speed,Hold Open Time, Half Opening distance, Opening, Direction,
5	Obstacle Detection	Permanent obstacle detection in both opening and closing cycles
6	Surface Treatment:	Silver Anodized
7	Safety	3D infrared curtain Photocell, Radar, opening radar with integrated curtain photocell, Energy
8	Glass	12 mm Toughened Glass
9	Interlocking	Two doors can be operated using interlocking mode
10	Compatibility	Compatibilty with Fire alarm and access control system
11	Energy Saving	Short braking distance during opening and closing cycle for Energy saving
12	Fault Monitoring	Error codes are shown on the digital position selector screen
13	Class of Protection	IP 22

Gear Operated Rolling Shutter

Sr .No.	Specification	MS Gear Operated Rolling Shutter
1	Description	Gear Operated Rolling Shutter with MS Laths with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete
4	Curtain Panel	The panel made of 1.0mm thick.
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	Hood Cover	Made of GI Sheet Thickness 1.2 mm GF mm with 25x25x3mm angle stiffener
11	Surface finish	2 Coats (each coat of 35 microns DFT) of EPOXY polyamide-based enamel finish of approved color and make over a Coat (each one coat 25 microns DFT) of EPOXY polyamide based red
12	Operation	Gear Assembly.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Amol Gaware on 7758820333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd