NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Tenneco Automotive India Pvt. Ltd.
122, Sipcot Industrial Complex,
Hosur, 635126
Tamil Nadu

Date : 21.08.2019
Quote NO : SQT.19.20.1953R
Kind Attn : Mr. Bala S
Email Id : BS@driv.com
Contact No: 7708440352

Project Name & Location: Hosur

Subject : Quotation for Albany Machine Protection Doors

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Albany make Machine Protection Door RP300**	1200	2150	2	5,50,000	11,00,000	18,000	36,000
2	**Supporting Structure required to mount the door**			2	25,000	50,000		-
				Total		**11,50,000**		**36,000**
4	P&F Charges			0%		-		
	Total Without Taxes					**11,50,000**		**36,000**
	GST Extra @ 18%					2,07,000		6,480
	Total With Taxes					**13,57,000**		**42,480**
5	Transportation Charges				**Included in Above Prices**			
6	Unloading Charges @ Site				**At Client Scope**			

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

High Speed door

Sr. No	Description	Details
1	Door version:	Vertical Rapid Roller Door for machine protection.
2	Side Frames:	Aluminum anodized two parts, to have easy access to switches and service.
3	Door blade:	RollTex Original, orange
4	Bottom beam	Aluminium anodized.
5	Drive unit:	Drive unit IP 55, either RH or LH as an option, with control cable (standard length = height of door)
6	Opening / closing speed:	Approx. max. 2,3 / 1,3 m/s
7	Control system:	MCC Vector Control
8	Power suppy:	3/(N)/PE 230/380/400/415 V, 50 Hz
9	Safety features:	Safety edge with cable chain integrated in side frames, pre running photocell.
10	Safety limit switch:	1 Schmersal safety limit switch PL e EN ISO 13849-1, SIL 3 EN 62061 on drive side integrated in the side frame to save space.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	NIHVA Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 11-12 Weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Arjun Patil on 8551096333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd