WORK ORDER

Client:	
Kohler India Corporation Pvt. Ltd	
Address:	
Plot No. 828, GIDC, Jhagadia, District Bharuch, Gujarat	

PO Number:	4200871850INJ3	**W. O. No-**	SO/23-24/001
PO Dated :	4/6/2023	**W. O. Date**	4/7/2023
PO Received Date:	4/6/2023	**Sales Co ordinator**	Shailesh
Ref. Quotation:	SQA.22.23_0244R2	**Front Sales Person**	

Dispatch Address:

Kohler India Corporation Pvt. Ltd.
Plot No.828,GIDC,Jhagadia,
393110 DISTRICT BHARUCH, GUJARAT

A Technical Terms:

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Supply Rate	Installation Rate	Total Amount	Dwg. Approval Status
1	**Alu High Speed Door with Only Push Button Operate Width 3000 mm Height 4000 mm**		**No**	**1**			**0**	**Pending**
						Total		-

Non standard items/extra requirement, if any:	**No deliveries accepted after 4:30 p.m. excluding Sundays/Holidays**

B	Commerical Terms:			
1	**Payment Terms:**	1. 70% Advance payment of Basic PO value against PDC valid till delivery Time 2. 20%+Taxes within 30 Days from the date receipt Goods 3. 10% within 30 Days after installation and commissioning		
2A	**Delivery Date as per PO:**	8-10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing	**2B. Required Delivery Date:**	
3A	**Transportation Scope:**	NIHVA Scope	**3B. Transportation Charges:**	
4	**P&F Charges:**	NIL		
5A	**Loading Scope:**	NIHVA Scope	**5B. Loading Charges:**	
6A	**Unloading Scope:**	CLIENT Scope	**6B. Unloading Charges:**	
7A	**Lifting Equipments Scope:**	CLIENT Scope	**7B. Available Lifting Equipments:**	
8	**Warranty:**	12 months from the date of supply.		
9A	**Height arrangement Scope:**	CLIENT Scope	**9B. Available Equipments for working at Site:**	
10	**Electricity Supply:**	CLIENT Scope		
11	**GST:**	18%		
12A	**Installation Scope:**	NIHVA Scope	**12B. Installation required date:**	
13	**Mode of import:**	NA		
14	**HSS:**	NA		
15	**Documentation Required:**	Standard Handover Documents		
16A	**Total site visits required:**		**16B. Site visit charges:**	

Certified that the above work order finalised in presence of:

GM	AGM	SALES		Operation	PROJECT	DESIGN	Date & Time
Mr. Ameet Kurhade		**Mr. Shailesh B**		**Mr. Kiran M**	**Mr. Sandeep M**	**Mrs. Sujata Biradar**	**20-04-2023**

Sr. No	Description	Specifications
1	**Use**	External Application
2	**Speed**	Inverter Motion system to adjust different speeds, with progressive control of acceleration & deceleration during braking
3	**Opening speed**	upto 2 m/s
4	**Closing speed**	0.7 m/s
5	**Control Panel**	3 Push Button operated
6	**Security Features**	EN 13241-1 Standard
7	**Resistance to wind load**	EN12424 upto class 1
8	**Curtain**	19 mm thk , Polyurethane filled RAL 9006 aluminium lamella
9	**Guide Material**	Aluminium Anodized , Painting in any RAL9006 lamalla colour
10	**Hood & Motor Cover**	Anodised Aluminum , Inclusive
13	**Operator & Control**	German Make Motor
14	**Connecting Voltage**	220V , 1Ph , N
15	**Open-Stop-Close Button**	Standarad
16	**Protection Category**	IP 54
18	**Emergency Off Button**	Standard
19	**Closing Zone Monitoring**	Optical Safety edge
20	**Safety Device**	Photocell
21	**Emergency Opening**	Crank Handle