NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

AG Group
Pune - 411014

Date : 11.11.2020
Quote NO : SQT.20.21.2823
Kind Attn : Gaurav kanade
Email Id : purchase@goelganga.in
Contact No: 9890793288

Project, Location : Pune

Subject : Quotation for Manual Swing Gate and Motorized Swing Gate.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Manual Swing Gate**	6000	3000	1	140,000	140,000	20,000	20,000
2	**Motorized Swing Gate**	6000	3000	1	170,000	170,000	20,000	20,000
	Total			**2**		**310,000**		**40,000**
3	P&F Charges			3%		9,300		
	Total Without Taxes					319,300		40,000
	GST Extra @ 18%			18%		57,474.00		7,200
	Total With Taxes					**376,774**		**47,200**
4	Transportation Charges					Extra at atcual		
5	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA make – Manual Swing Gate

Sr. No	Specification	Motoriszed Bi-Parting Swing Gate & Wicket Gate
1	Wicket Gate Leaf Size	6000 x 3000 mm
2	Clear Opening gate dimension	6000 x 3000 mm
3	Opening Direction	left to right or reverse
4	Outer Tube	72 X 72 X 3.2 MM THK SQ. TUBE
5	Inner Tube	25 X 25 X 2.6 MM THK SQ. TUBE
6	Gap Between Tubes	125mm
6	Design Pattern	Standard Tubular Design Pattern
7	Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
8	Civil work	Client scope

NIHVA make – Motorized Swing Gate

Sr. No	Specification	Motoriszed Bi-Parting Swing Gate & Wicket Gate
1	Wicket Gate Leaf Size	6000 x 3000 mm
2	Clear Opening gate dimension	6000 x 3000 mm
3	Opening Direction	left to right or reverse
4	Outer Tube	80 x 40 x 3.2 mm THK SQ. TUBE
5	Inner Tube	40 x 40 x 2.6 mm THK SQ. TUBE
6	Gap Between Tubes	125mm
7	Design Pattern	Standard Tubular Design Pattern
8	El motor make	BFT – Italy (100% imported)
9	Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
10	Civil work	Client scope
11	Emergency Operation	Manual after turn the switch

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Amol Gaware on 7758820333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd