NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/17-18/0100 **01-03-2018**

Ordnance Factory Dehuroad
Shelarwadi, Dehu Road Contonment
Dehu Road Maharashtra 412101

Kind Attn : Mr. T K Panda
Email : ofdreo.ofb@gov.in
Contact No : 020 -27671206/09


Subject : Quotation for Manipulator,Rail & Roller Conveyor

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.

This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr.No	Description	Qty	Unit	Rate In INR	Net Amount INR
	Manipulator : 1. Manipulator enables the safe and efficient handling of many products up to a maximum weight of 50 kg. 2. Manipulator incorporates a pneumatic cylinder to achieve the lifting action, and is normally custom built to suit the relevant working environment 3. Low noise levels and low maintenance make manipulator the ideal solution for your material handling problems 4. Three control styles ensure maximum flexibility. Auto balance, powered lift/lower, and pre-set loaded/unloaded options allow the most suitable control style to be used for each handling application.				
					
A	**Rail Mounted Manipulator**				
1	Manipulator Type : Pneumatic	**1**	**No.**	**8,30,000**	**8,30,000**
	Manipulator 6 Bar , Capacity : 50 kg				
	Maximum working Radius / Span : 3000 mm				
	Minimum Vertical Lift from Floor : 300 mm				
	Maximum Vertical Lift from Floor : 1400 mm				
	Air Booster with Tank	**1**	**No.**	**1,30,000**	**1,30,000**
	Hook for Lifting with pendulum				
	12 X 7 meter Roof Mounted Railing System	**1**	**No.**	**7,52,000**	**7,52,000**
	I Beam Structure	**2**	**No.**	**3,30,000**	**6,60,000**
	Installation charges for above Manipulator	**1**	**No.**	**40,000**	**40,000**
A	**Total**	**1**	**Set**		**24,12,000**
B	**Roller Conveyor For Truck Unloading**				
1	Length Of Conveyor : 4 meter	**1**	**Nos**	**4,80,000**	**4,80,000**
2	Application: For manual unloading				
3	Conveyor Type : Roller Conveyor				
4	**Installation Charges For Roller Conveyor**	**1**	**No**	**22,000**	**22,000**
B	**Total**	**1**	**Set**		**5,02,000**

GST PUNE :	**27AAECN0437H1ZM**
HSN CODE :	**8428.90.90**

Amount In Words	**Total (A+B)**	**29,14,000**
	Rupees Twenty Nine Lacs Fourteen Thousand Only	

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	3% Extra as applicable.
3	**Freight Notes**	:	Extra as applicable.
4	**Delivery**	:	8-10 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% advance along with confirm Purchase Order & balance before dispatch
6	**Insurance**	:	Extra as applicable.
7	**GST**	:	Extra as Applicable on total supply value.
8	**Validity**	:	Validity of Offer is 15 days from the of quotation
9	**Warranty**	:	12 Months from the date of supply

Please feel free to Contact **Mr. Mayur Derle** on **7709209333** For any further Clarification /Information in this Concern.

With Best Regards

Pooja Badre

7709586333

For Nihva Technologies Pvt Ltd