BAG FILLING
(1) 5 Kg (NEW)

BIG BAG 350 Kg per bag | BIG BAG 350 Kg per bag

6000 Kg/hr

CHARGING SILO IN QUARANTINE

Vacuum Transfer

SILO - 1

(20 PPM FILLING)

POUCH FILLING
(2) 1Kg (NEW)

BIG BAG 350 Kg per bag

3000 Kg/hr

CHARGING SILO IN QUARANTINE

Vacuum Transfer

SILO - 1

(50 PPM FILLING)

CASE LINER FILLING
(3) & (4) 500 gms (1NEW) (1OLD)

BIG BAG 350 Kg per bag

(65PPM) (NEW) +(35PPM) (OLD)

3000 Kg/hr

CHARGING SILO IN QUARANTINE

Vacuum Transfer

SILO - 1 (65 BPM FILLING) | SILO - 2 (35 BPM FILLING)

POUCH FILLING
(5) & (6) 250 gms (2NEW)

BIG BAG 350 Kg per bag

3600 Kg/hr

CHARGING SILO IN QUARANTINE

Vacuum Transfer

SILO - 1 (120 PPM FILLING) | SILO - 2 (120 PPM FILLING)

POUCH FILLING
(7) & (8) 250 gms (1NEW) (1OLD)

BIG BAG 350 Kg per bag

3600 Kg/hr

CHARGING SILO IN QUARANTINE

Vacuum Transfer

SILO - 1 (120 PPM FILLING) | SILO - 2 (120 PPM FILLING)

POUCH FILLING
(9) 100 gms (NEW)

BIG BAG 350 Kg per bag

900 Kg/hr

CHARGING SILO IN QUARANTINE

Vacuum Transfer

SILO - 1

Tiwn Line
(150 PPM FILLING MACH.)

POUCH FILLING
(10) & (11) 30 - 50 gms Rs. 10 /-

BIG BAG 350 Kg per bag (1NEW) (2EXISTING) (1PROVISION)

3600 Kg/hr

CHARGING SILO IN QUARANTINE

Vacuum Transfer

(300 PPM) | (300 PPM) | (300 PPM) | (300 PPM)

SILO - 1 | SILO - 2 | SILO - 3 | SILO - 4

MACH.-1 (300 PPM FILLING MACH.) | MACH.-2 (300 PPM FILLING MACH.) | MACH.-3 (300 PPM FILLING MACH.) | MACH.-4 (300 PPM FILLING MACH.)

POUCH FILLING
(12) & (13) 25 gms - 16 gms Rs. 5/-

BIG BAG 350 Kg per bag (3NEW) (1PROVISION)

1800 Kg/hr

CHARGING SILO IN QUARANTINE

Vacuum Transfer

(300 PPM) | (300 PPM) | (300 PPM) | (300 PPM)

SILO - 1 | SILO - 2 | SILO - 3 | SILO - 4

(300 PPM FILLING MACH.) | (300 PPM FILLING MACH.) | (300 PPM FILLING MACH.) | (300 PPM FILLING MACH.)

(14) JAR FILLING(NEW)

BIG BAG 350 Kg per bag

2400 Kg/hr

CHARGING SILO IN QUARANTINE

Vacuum Transfer

SILO - 1

(1Kg 40 BPM FILLING MACH.)

POUCH FILLING
(15) & (16) (EXISTING)

BIG BAG 350 Kg per bag

(160 PPM) 720 Kg/hr

CHARGING SILO IN QUARANTINE

Vacuum Transfer

SILO - 1 (Tiwn Line 50 gms Rui Dust (160 PPM FILLING MACH.)) | SILO - 2 (Tiwn Line 25 gms Rui Dust (160 PPM FILLING MACH.))

(NEW) POUCH FILLING
(17) 500 gms (1NEW)

BIG BAG 350 Kg per bag

3600 Kg/hr

CHARGING SILO IN QUARANTINE

Vacuum Transfer

SILO - 2 (120 PPM FILLING MACH.)

(NEW) POUCH FILLING
(18) 250 gms (NEW)

BIG BAG 350 Kg per bag

3600 Kg/hr

CHARGING SILO IN QUARANTINE

Vacuum Transfer

SILO - 2 (240 PPM FILLING MACH.)

Please refer :- 1) Drg. no. DTS/272/11(R34) on date 12.12.2016 Layout drg. of GF MPB
2) Through Put Chart Revised on date 09.12.2016

REV.	DATE	DESCRIPTIONS
R2	22.12.2017	CORRECTED CHART
R1	30.12.2016	CORRECTED CHART

D R G NO - DTS/272/187
DATE - 12/12/2016
SCALE - 1:100
DRNBY : **BHARTI**
JOB TITLE - PROPOSAL PROJECT FOR AMAR TEA PLANTATION AMAR TEA UMARGAOAN
OWNER- **AMER TEA PVT LTD.**
TITLE OF DRG -FLOW CHART

NORTH

ARCHITECT
MINAL MEHTA
COUNCIL OF ARCHITECTURE. (GOVT. OF INDIA)
REGN.NO -CA/93 /16194

PROJECT MANAGEMENT CONSULTANTS
DEV TECHNOSKILLS
AMRUTNAGAR RD
GHATKOPAR (W)
MUMBAI 86