NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/17-18/0082 **Date : 22-12-2017**

Kals Distilleries Pvt Ltd
Kallaakottai, Tamil Nadu 622302

Kind Attn : Mr. Prabhu.S
Email : sprabhu@kals.co.in
Contact No : 9442504036

Subject : Quotation for Telescopic Conveyor

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr.No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Telescopic Conveyor Make - NIHVA (HSN CODE : 84289090) 15 meter length**				
	• Length of Conveyor : 15000 mm • Extended Length of Conveyor : 9445 mm • Fixed Length of Conveyor : 5000 mm • Width of Conveyor : 500 mm • Material to be handle : Carton box / Gunny Bags • Weight of Material : 50 kgs • Material of Construction : MS Painted • Loading Height From Shop Level : 5465 mm • Speed Of Conveyor : 30 mtr/min Max. • Temperature : Ambient • Drive Motor : 5 HP Coupled Geared Motor • Castor wheels for manual movement • Stepper Motor, Sensor and Control Panel	**1**	**No**	**20,23,000**	**20,23,000**
B	**Telescopic Conveyor Make - NIHVA; 11 meter length**				
	• Length of Conveyor : 11000 mm • Extended Length of Conveyor : 6239 mm • Fixed Length of Conveyor : 4226 mm • Width of Conveyor : 500 mm • Loading Height From Shop Level : 4263 mm • Other details are same as above	**1**	**No**	**14,98,000**	**14,98,000**
C	**Installation ,Comissioning & Training Charges**	**1**	**No**	**10,000**	**10,000**

GST PUNE:	**27AAECN0437H1ZM**
GST GUJRAT:	**24AAECN0437H1ZS**

Amount in Words	**Total Amount**	**35,31,000**
	Rupees Thirty Five Lacs Thirty One Thousand Only	

Image Attached For your Reference



Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
3 Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel.

Client Scope

1 Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2 All structure support is in client scope
3 NIHVA Will provided structure drawing only if required
4 Existing Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	3% Extra
3	**Freight Notes**	:	Extra as applicable
4	**Delivery**	:	8-9 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% advance along with confirm Purchase Order & balance before dispatch
6	**Insurance**	:	Extra if applicable
7	**Tax**	:	GST: Extra as applicable on total supply value
8	**Validity**	:	Validity of Offer is 15 days from the of quotation
9	**Warranty**	:	12 Months from the date of supply

Please feel free to Contact **Mr. Mayur Derle** on **7709209333** For any further Clarification /Information in this Concern.

With Best Regards

Pooja Badre
7709586333
For Nihva Technologies Pvt Ltd