NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Suroj Buildcon Pvt Ltd
Pune

Date : 24.10.2019
Quote NO : SQT.19.20.1729R
Kind Attn : Mr. Prashant Raut
Email Id : praut@suroj.in
Contact No: 777 401 4847

Project Name & Location: MANE INDIA DAHEJ

Subject : Quotation for High Speed Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
Option 1 : High Speed Door with SS Material								
1	**HIGH SPEED PVC ROLL UP DOOR**	2700	3100	6	346,000	2,076,000	18,000	108,000
2	**HIGH SPEED PVC ROLL UP DOOR**	2200	3100	25	338,000	8,450,000	18,000	450,000
3	**HIGH SPEED PVC ROLL UP DOOR**	3000	3100	6	352,000	2,112,000	18,000	108,000
4	**HIGH SPEED PVC ROLL UP DOOR**	1400	3100	2	310,000	620,000	18,000	36,000
					Total	13,258,000		702,000
			P&F Charges	3%		**397,740**		
			Total Without Taxes			**13,655,740**		**702,000**
			GST Extra @ 18%	18%		2,458,033		126,360
			Total With Taxes			**16,113,773**		**828,360**
Option 2 : AL Material								
1	**HIGH SPEED PVC ROLL UP DOOR**	2700	3100	6	306,000	1,836,000	18,000	108,000
2	**HIGH SPEED PVC ROLL UP DOOR**	2200	3100	25	298,000	7,450,000	18,000	450,000
3	**HIGH SPEED PVC ROLL UP DOOR**	3000	3100	6	312,000	1,872,000	18,000	108,000
4	**HIGH SPEED PVC ROLL UP DOOR**	1400	3100	2	270,000	540,000	18,000	36,000
					Total	11,698,000		702,000
			P&F Charges	3%		**350,940**		
			Total Without Taxes			**12,048,940**		**702,000**
			GST Extra @ 18%	18%		2,168,809		126,360
			Total With Taxes			**14,217,749**		**828,360**
			Transportation Charges			**In Client Scope**		
			Unloading Charges @ Site			**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

HIGH SPEED PVC ROLL UP DOOR



- Safe & for continous operations
- Self Supporting Construction with anti crash protection system for bottom profile
- Smooth & silent opening & closing
- Can be equipped with full vision PVC curtain
- Modular Interchaegable panels permit to replace worn & damged panels

Sr. No	Description	Specifications - SS Door	Specifications - Al Door
1	Use	Internal Door	Internal Door
2	Speed	Inverter Motion system to adjust different speeds, with progressive control of acceleration & deceleration during braking	Inverter Motion system to adjust different speeds, with progressive control of acceleration & deceleration during braking
3	Opening speed	3 m/s	3 m/s
4	Closing speed	0.8 m/s	0.8 m/s
5	Control Panel	4 Push Button operated	4 Push Button operated
6	Security Features	EN 13241-1 Standard	EN 13241-1 Standard
7	Resistance to wind load	EN12424 upto class 2	EN12424 upto class 2
8	curtain	Fabric Transparent PVC section	Fabric Transparent PVC section
9	Guide Material	Stainless Steel	Aluminum
10	Hood Cover	Stainless Steel	GI
11	Motor Cover	Stainless Steel	GI
12	Operator & Control	German Make Motor	German Make Motor
13	Connecting Voltage	220V , 1Ph , N	220V , 1Ph , N
14	Open-Stop-Close Button	Standarad	Standarad
15	Protection Category	IP 54 / IP 65	IP 54 / IP 65
16	Power Consumption	0.75 kw Motor	0.75 kw Motor
17	Emergency Off Button	Standard	Standard
18	Closing Zone Monitoring	Optical Safety edge	Optical Safety edge
19	External Route Monitoring	Photocell	Photocell
20	Emergency Opening	Crank Handle	Crank Handle

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain on 8551092333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd