NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Design Tech Studio

Date : 08.02.2020
Quote NO : SQT.19.20.2417
Kind Attn : Ms. Priya
Email Id : designtechstudio@gmail.com
Contact No: **9730157990**

Subject : Quotation for Sectional Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Sectional Door (Standard Lift)	6000	2600	1	3,28,000	3,28,000	20,000	20,000
				Total		**3,28,000**		**20,000**
				P&F Charges	3%	**9840**		
				Total Without Taxes		**3,37,840**		**20,000**
				GST Extra @ 18%	18%	60,811.20		3,600
				Total With Taxes		**3,98,651**		**23,600**
				Total Supply + Installation with Taxes				**4,22,251**
2				Transportation Charges		**In Client Scope**		
3				Unloading Charges @ Site		**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

ASSA ABLOY Motorised Sectional Door

Sr. No	Description	Specification
1	Model No	ASSA ABLOY OH1042P
2	Opening/Closing Speed	CDM9 0,28 m/s
3	Door Material	Steel
4	Panel Thickness	42 mm Square Grid, steel sheet
5	Filling	CFC-free polyurethane
6	Door sealent	All door sealants made of EPDM rubber, temperature resistant -30/+70
7	Water Penetration	EN 12425 class 3
8	Air Permealibity	EN12426 class 3
9	Thermal Transittance	EN 12428 1.10W /m2K
10	Bottom sealing	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
11	Door saftey	Doors equiped with spring break device
12	Incase of Power failuer	Doors to be equiped with quick release fuction
13	Operator power conumption	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W
14	Drive Unit & Mounting Type	Single phase 230V direct drive on shaft
15	Emergency Operation	by Disengagement rope manual
16	Operating Switch	Up/Down Keypad + stopbutton
17	Locks : Lock bolt	The Lock bolt locks the door from the inside, without the use of a key. The Lock bolt is not visible from the outside.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope
8	Steel structure for Dock House & Sectional Door	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 7 - 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333**

With Best Regards
Vivek
8350570333
For NIHVA Technologies Pvt Ltd