Ref No.:-20-21/GEN/ENQ/ 440 Date: 09 September 2020

To,

M/S Nihva Technologies Pvt. Ltd.
G Block Thermax chowk
Above Renault showroom
Chinchwad, Pune-411019

Kind attention
Mr. Vijay Tarak
Nigdi, Pune
Maharashtra- 411044

Dear Sir,

Subject: - Quotation for supply installation testing and commissioning of passenger elevator.

Reference: - As per our discussion at your site

We are thankful to you for providing us an opportunity to serve you with our best quality product and technical excellence. We undertake this opportunity to introduce ourselves as one of the fastest growing ISO 9001: 2015 certified Elevator Company in Maharashtra India with latest highly advanced global technology of micro processer based control panel with Serial Communication System and Gearless Machine Techniques at our
Indoor facility, which ensure the reliability and performance of the equipment.

We hereby submit our best quotation for your requirement and, waiting for
Your valuable response to furnish further details.

Thanking you and assuring the best of our services for all the time.

Yours faithfully

For **VERTEX ELETECH PVT.LTD.**

TECHNICAL SPECIFICATION:-

PRODUCT	GOODS LIFT MANUAL DOOR
CAPACITY	2500 KG
SPEED	0.25 M/S
CAR TRAVEL	G+4
NO OF STOPS	FIVE STOPS
NO OF OPENNG	FIVE OPENINGS (ALL OPENNING ON THE SAME SIDE)
DRIVE	NA
MAIN POWER SUPPLY SYSTEM	415 VOLTS, 3 PHASE, 50 HZ A.C. (CLIENT SCOPE)
LIGHT SUPPLY	230 VOLTS, SINGLE PHASE 50 HZ A.C. (CLIENT SCOPE)
MACHINE	HYDRAULIC TRACTION MACHINE
LANDING DOOR FINISH	MANUAL COLLAPSIBLE DOOR
CAR DOOR FINISH	MANUAL COLLAPSIBLE DOOR
DOOR OPENNING	1200 MM CLEAR DOOR OPENNING
CAR SIZE	1600MM WIDTH AND 2000MM DEPTH (SIZE CAN BE CHANGES AS PER GAD)
CAR FINISH	MILD STEEL POWDER COATED (MADE BY HIGH QUALITY PRECOATED SHEET)
CAR FLOORING	M.S. PLATE
FALSE CEILING	MILD STEEL POWDER COATED
HAND RAIL	NA
ELEVATOR ROPE	USHA MARTIN (DUAL STRENGTH)
ELEVATOR WELL	1800 MM WIDTH, 2500 MM DEPTH (INSIDE FINISHED)
MACHINE ROOM	AS PER REQUIRED
ELEVATOR PIT	500 MM DEPTH
SPEED GOVERNOR	NA
FIREMAN OPTION	NA
CONTROL SYSTEM	SIMPLEX DOWN COLLECTIVE CONTROL PANEL
CONTROLLERTYPE	MICROPROCESSOR BASE CONTROL PANEL
SIGNALS	1) UP/DOWN DIRECTION INDICATORS AT ALL LANDING 2) DIGITAL CAR POSITION INDICATORS

COMMERCIAL OFFER:-

Sr. No.	Description	Qty	Unit 0f Measure	Unit Price	Amount
1	2500 KG with rated speed 0.25M/Sec G+4 manual doors	1	Nos.	18,00,000.00	18,00,000.00
	TOTAL COST				

Total amount in words: - Eighteen lakh rupees only

TAXES EXTRA AS APPLICABLE: -

1) CGST as per government standard
2) SGST as per government standard

TERMS & CONDITIONS:-

1) Validity – 30 days from the date of submit.

PAYMENT SLABS:-

1) 20% of the contract value in advance, along with order confirmation.
2) 50% of the contract value against commencement of material procurement.
3) 20% of the contract value on commencement of installation of elevator.
4) 10% of the contract value before hand over the elevator

WARRANTY & FREE MAINTENANCE:-

1) Vertex Elevators warranty only the material and workmanship of the equipment For a period of twelve (12) months, from the date of completion of validity period.
2) The warranty covers repair and replacement of the defective parts only and Do not cover any consequential resulting liabilities, damages or losses

DOCUMENTS REQUIRED FOR ELEVATOR LICENSE:-

1. Sanctioned Building Plan Xerox copy with Notary
2. Commencement certificate
3. Architect Certificate.
4. Structure engineer Certificate.
5. Owner Letter with signature
6. Owners identity proof Adhar card/ Driving licence
7. Passport size Photograph

You are requested to kindly make payment by crossed cheque/demand draft/pay order Or NEFT/RTGS In favor of M**/S Vertex Eletech Pvt. Ltd.**

PREPARATORY WORK:-

1. To be provided site details and drawings required for starting work on the project
2. To be provided a completely enclosed elevator hoist way with all walls duly finished and painted with lift pit of required depth.
3. To be provided painted and ventilated machine room of sufficient size to accommodate lift equipments.
4. To be provided and install necessary hoist way door frames, fascia plates and architraves.
5. To be provided sill projection for each hoist way entrance to assure secured anchorage & support of each sill.
6. To be provided hoist way structure of such a design that can withstand the impact and loads resulting from the use of elevator.
7. To be provided civil work support for lift installation
8. To do all cutting of walls, floor, together with any repair made necessary thereby. This includes grouting of all bolts, sills, steel members, indicator and push button boxes etc in position.
9. To be provided and installed power and power connection as follows
   a. A fused Circuit Breaker of suitable rating for elevator
   b. A fused Circuit Breaker for lift lighting circuit.
   c. A fused Circuit Breaker for hoist way lighting circuit in the hoist way at each floor level.
   d. A separate earthing pit as per latest Indian electricity rules and double earthing connection brought in the machine room.
   e. ELCB of suitable capacity.
10. To be provided sufficient lighting and necessary power supply for elevator installation on customer expense, electric power for power tools in hoist way and testing of elevators
11. To be protect the hoist way entrance by suitable means during the process of lift installation at site.
12. To be provided scaffolding in the hoist way as per our technical requirements and to remove the same alter completion of the installation.
13. To be provided suitable lockable storage spaces for elevator material near the lift hoist way..
14. To be provided hoisting beam in the machine room and rolled steel “I” section as mentioned for support of the machine and ‘c’ section I beam the lift well divider of appropriate size.
15. The unloading of lift material would be done by our manpower. However, any monetary consideration towards labor union or hamal panchayat of your site area exists , the same will have to be taken care and paid by you

If you have any queries for above documents so please call on 07776076662/020 27279009

For customer Name	For Vertex Name
Authorized signatory Sign with stamp	Authorized signatory Sign with stamp