**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2008 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**Serum Institute**
Pune

**Date : 22.12.2020**
Quote NO : SQT.20.21.2717R3
**Kind Attn :** Mr. Pradip Paithane
Email Id : pradip.paithane@seruminstitute.com
Contact No: 9881836006

**Project Name & Location:**

**Subject : Quotation for Automatic Telescopic Sliding Glass Door**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.**


| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |


**A) Commercial Offer**

| Sr No | Description | Location | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|---|
| | | | Clear Width (mm) | Clear Length (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **Automatic Biparting Sliding Glass Door System 100 % Imported Operator - Hafele Make** | **Admin Building** | 2000 | 2530 | 1 | 200,000 | 200,000 | 10,000 | 10,000 |
| 2 | **Automatic Telescopic Sliding Glass Door System 100 % Imported Operator - Hafele Make** | **SEZ 1** | 2070 | 2400 | 2 | 335,000 | 670,000 | 10,000 | 20,000 |
| | | | | | **Total** | | **870,000** | | **30,000** |
| 3 | P&F Charges on Total Supply Value | | | | 0% | | | | |
| | GST Extra @ 18% | | | | 18% | | **156,600** | | **5,400** |
| 4 | Transportation Charges | | | | | | **Inclusive** | | |
| 5 | Unloading Charges @ Site | | | | | | **In client scope** | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2008 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**Automatic Sliding Glass Door System**

| Sr. No | Description | Specifications |
|---|---|---|
| 1 | Motor | High performance and heavy duty DC motor with integrated encoder and gearbox |
| 2 | Power Supply | 170-260 V AC 50-60 Hz |
| 3 | Power Consumption | 170 W |
| 4 | Protection Class | IP 22 |
| 5 | Carrying Capacity | 170 Kg for single leaf, 240 Kg for double leaves |
| 6 | Operator | Hafele Make - 100% Imported |
| 7 | Operator Chassis Size | 125 x 168 mm , Aluminium |
| 8 | Carrier Assembly | Two carrier assembly for each leaf, (2 main and 1 balancing wheel for each carrier assembly) |
| 9 | Trigger Belt | Special trigger belt design for maximum safety and endurance and minimum noise level |
| 10 | Working Temperature | - 20* C + 50* C |
| 11 | Position Selector | Digital , 6 user positions, LCD touch screen |
| 12 | User Modes | Auto , Open , In , Out , Locked , Partial Opening |
| 13 | Installer Settings | Opening Speed, Closing Speed, Hold Open Time, Half Opening Distance, Opening, Direction, Installer Password, User Password |
| 14 | Obstacle Detection | Permanent obstacle detection in both opening and closing cycles. |
| 15 | Energy Saving | Short braking distance during opening and closing cycle for energy saving |
| 16 | Interlocking | 2 doors can be operated using interlocking mode |
| 17 | Resetting | Can be performed using digital position selector without opening operator cover |
| 18 | Compatibility | Compatible with fire alarm and access control systems |
| 19 | Fault Monitoring | Error codes are shown on the digital position selector screen. |
| 20 | Safety | 3D infrared curtain photocell |
| 21 | Opening Sensor | Radar |
| 22 | Combiner (Opening + Safety) Sensor | Opening radar with integrated 3D infrared curtain photocell, Energy saving, EN16006 |
| 23 | Door Leaf | Frameless With 2 point fittings per door panel |
| 24 | Glass | 12mm thick Glass |
| 25 | Operator Mounting | On glass panel provided by others |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2008 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site | NIHVA Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | Client Scope |
| 4 | Any civil / masonry/structural work required | Client Scope |
| 5 | All structure support required | NIHVA Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | Client Scope |
| 7 | Conduits, Cables required | Client Scope |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 8 - 9 Weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 100% Against delivery of material

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Arjun Patil on 8551096333**

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd