NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Lupin Limited
Aurangabad

Date : 08.12.2020
Quote NO : SQT/20-21/2874
Kind Attn : Mr.Dilip Khandade
Email Id : dilipkhandade@lupin.com
Contact No: 0240-6612272

Subject : Quotation for NIHVA make High Speed Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Nihva Make High Speed Door - Internal Application - Raw material Stores(This is option for Assa Abloy make Door already quoted by quote number - SQT 20.21.2868 dt. 05.12.2020)	2000	1900	1	2,37,000	2,37,000	20,000	20,000
2	Nihva Make High Speed Door - Internal Application - Raw material Store	2000	2400	1	2,49,000	2,49,000	20,000	20,000
3	Automatic Sliding Doors	1800	2100	1	1,63,000	1,63,000	20,000	20,000
4	Automatic Sliding Doors	1800	2200	1	1,63,000	1,63,000	20,000	20,000
5	Automatic Sliding Doors	1950	2100	1	1,63,000	1,63,000	20,000	20,000
6	Accessories - Inter Locking			1	18,000	18,000		-
				Total		**9,93,000**		**1,00,000**
7	P&F Charges			3%		29,790		
	Total Without Taxes					10,22,790		1,00,000
	GST Extra @ 18%			18%		1,84,102.20		18,000
	Total With Taxes					**12,06,892**		**1,18,000**
8	Transportation Charges					Extra at Actual		
9	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Make HIGH SPEED PVC ROLL UP DOOR

- Safe & for continous operations
- Self Supporting Construction with anti crash protection system for bottom profile
- Smooth & silent opening & closing
- Can be equipped with full vision PVC curtain
- Modular Interchaegable panels permit to replace worn & damged panels



Sr. No	Description	Specifications
1	Use	Internal Door
2	Speed	Inverter Motion system to adjust different speeds, with progressive control of acceleration & deceleration during braking
3	Opening speed	1 m/s
4	Closing speed	1 m/s
5	Control Panel	4 Push Button operated
6	Security Features	EN 13241-1 Standard
7	Resistance to wind load	EN12424 upto class 1
8	Curtain	Fabric Transparent PVC section
9	Guide Material	Aluminum
10	Hood Cover	GI
11	Motor Cover	GI
12	Operator & Control	German Make Motor
13	Connecting Voltage	220V , 1Ph , N
14	Open-Stop-Close Button	Standarad
15	Protection Category	IP 54 / IP 65
16	Power Consumption	0.75 kw Motor
17	Emergency Off Button	Standard
18	Closing Zone Monitoring	Optical Safety edge
19	External Route Monitoring	Photocell
20	Emergency Opening	Crank Handle
21	Feature	airtight and designed for cleanrooms and other areas with a controlled or filtered atmosphere
22	Inter Locking	can be included at exta cost

Automatic Sliding Glass Door



Sr. No	Description	Specifications
1	Operator Type	Bi part operator.
2	User Modes	Auto, Open, In,Out, Locked, Partial opening
3	Operator Dimension	125 x 168 mm
4	Installer Settings	Opening speed, Closing Speed,Hold Open Time, Half Opening distance, Opening, Direction, Installer Password, User Password
5	Obstacle Detection	Permanent obstacle detection in both opening and closing cycles
6	Surface Treatment:	Silver Anodized
7	Safety	3D infrared curtain Photocell, Radar, opening radar with integrated curtain photocell, Energy saving EN16006
8	Glass	12 mm Toughened Glass
9	Interlocking	Two doors can be operated using interlocking mode
10	Compatibility	Compatibilty with Fire alarm and access control system
11	Energy Saving	Short braking distance during opening and closing cycle for Energy saving
12	Fault Monitoring	Error codes are shown on the digital position selector screen
13	Class of Protection	IP 22

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	
3	Electrical Supply on the site single phase/three phase points at different places.	
4	Any civil / masonry/structural work required	
5	All structure support required	
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	
7	Conduits, Cables required	

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 -8 weeks for High Speed Doors from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mrs. Sneha Bharane on 8551035333** For any further Clarification /Information in this Concern.

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd