NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No -SQT/19-20/1777 **Date 02.07.2019**

REECA INFRASTRUCTURE PVT LTD
114, 115, Race Course Towers, Race course
Vadodara - 390007

Kind Attn : Mr. Jwalit Jani
Email ID : purchase.reeca@gmail.com
Contact No : 7567305005

Project Name And Location : Munjal Auto Plant

Subject : Quotation for Motorized Rolling Shutter.

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Motorized Rolling Shutter** **Technical Specifications:** **• MS Slat : 1.0 mm Thick** **• Profile : Curved Type Profile with heavy duty Shaft** **• Guide : 2.5 mm Thick MS Guide** **• Hood Cover & Motor Cover : 0.9 mm Thick GI material** **• Indirect Drive** **• With Painting** **(Supply + Installation)**				
1	Size (W) 6000 mm x (H) 7500 mm	6	Nos.	311,000	1,866,000
2	Size (W) 4000 mm x (H) 4000 mm	13	Nos.	141,000	1,833,000
3	Size (W) 1200 mm x (H) 1800 mm	2	Nos.	68,000	136,000
4	Size (W) 3000 mm x (H) 3000 mm	5	Nos.	106,000	530,000
5	Size (W) 4000 mm x (H) 3500 mm	8	Nos.	131,000	1,048,000
6	**Motorised Rolling Shutter with Grill** Size (W) 3000 mm x (H) 3000 mm	1	No.	149,000	149,000
7	**Motorised Rolling Shutter with Grill** Size (W) 4000 mm x (H) 4000 mm	2	Nos.	112,000	224,000
				Total	5,786,000

GST Pune	**27AAECN0437H1ZM**	**Grand Total**	**5,786,000**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@ 3% of Total supply value
3	**Freight Notes**	:	Extra as applicable + Taxes
4	**Delivery**	:	5-6 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Insurance**	:	Extra As applicable
8	**Tax**	:	GST@18% Extra
9	**Validity**	:	Validity of Offer is 15 days from the date of quotation
10	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Bhavin** on **8551092333** For any further Clarification /Information in this Concern.

With Best Regards

Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd