NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Skoda Auto Volkswagen India Private Limited
Aurangabad

Project, Location : Aurangabad_Chakan

Date : 29.03.2027
Quote NO : SQT.20.21.3073R
Kind Attn : Prasad. Gaikwad
Email Id : 'prasad.gaikwad@skoda-vw.co.in'
Contact No: 9607900538

Subject : Revised Quotation for High Speed Doors - HS 8010PL & HS 8010P

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**ASSA ABLOY High Speed Door - HS8010PL, Structure Modification, Scafolding - control panel on both side. (BLOCK STORAGE - HALL C)**	5735	4100	1	1,352,000	1,352,000	Inclusive	
2	**ASSA ABLOY High Speed Door - HS8010P, Structure Modification, Scafolding (DOCK NO - 4 , HALL C)**	3416	4000	1	853,000	853,000	Inclusive	
3	**ASSA ABLOY High Speed Door - HS8010P, Remote Control, Structure Modification, Scafolding (DOCK NO - 5 , HALL C)**	3435	4000	1	853,000	853,000	Inclusive	
4	**ASSA ABLOY High Speed Door - HS8010P , Structure Modification, Scafolding (DOCK NO - 6 , HALL D)**	3000	3545	1	836,000	836,000	Inclusive	
5	**ASSA ABLOY High Speed Door - HS8010PL with Radar on both side, Interlocking, Remote Control, Structure Modification, Scafolding (HALL C - VESTIBULE)**	5970	4000	1	1,394,000	1,394,000	Inclusive	
6	**ASSA ABLOY High Speed Door - HS8010PL with Loop Detector, Radar, Interlocking, Remote Control, Structure Modification, Scafolding (HALL C - VESTIBULE)**	5715	4000	1	1,396,000	1,396,000	Inclusive	
7	**Removing of Existing Sectional Overhead Door**			6	25,000	150,000		
	Total			**12**		**6,834,000**		-
8	P&F Charges			0%		-		
	Total Without Taxes					6,834,000		-
	GST Extra @ 18%			18%		1,230,120.00		-
	Total With Taxes					**8,064,120**		-
9	Transportation Charges					Inclusive		
10	Unloading Charges @ Site					Inclusive		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

ASSA ABLOY High Speed Door - HS8010PL

Sr. No	Description	Specifications
1	Structure	Galvanized steel
2	Colours	8 standard colors - white, yellow, green, orange, red, gray, black, blue
3	Safety	• Photocells in side columns • Flexible soft bottom edge including wireless edge activator • Break-away and self-repair function
4	Operation	Operator + control unit
5	Operating speed	opening: up to 1,4 m/s ; closing: up to 0,6 m/s
6	Wind load resistance	class 3 (700 N/m2) class 4 (1000 N/m2) for doors up to 6000 x 5500 mm
7	Air permeability	Class 1 (24 m3/m2/h at 50 Pa) EN 12426
8	Water penetration	class 1 (30 N/m2)
9	Thermal transmittance	6,02 W/(m2K)
10	Performance Test	750.000 cycles
11	Temperature working range	0 °C to +40 °C
12	Vision window	Horizontal one row of height 400 mm at eye level

ASSA ABLOY High Speed Door - HS8010P

Sr. No	Description	Specifications
1	Door construction:	The HS8010P is designed for exterior openings in medium-sized heavy-duty operations
2	Side Frames	Made up with Galvanised Steel Profiles. Unique side column technology provides excellent seal on all 4 sides thereby reducing heat loss
3	Door Curtain	• Door curtain 900 g/m² colored PVC, material thickness: 0,8 mm • Flexible door curtain without ridged parts. • The door curtain is available in 8 standard colors
4	Thermal transmittance:	(EN 12428) 6,02 W/(m²K)
5	Wind resistance:	(EN 12424) Class 4 (1000 Pa (N/m²))
6	Drive Unit :	1,5 KW. 400V, 3 Phase
7	Temperature range :	-20°C to +40°C
8	Operator protection:	IP65
9	Control system:	Control unit with display, impulse Up and Down buttons, an emergency stop mushroom button and a mechanical main switch
10	Speed:	Opening / closing up to 2,4 / 1,2 m/s. Depends on Door Size
11	Safety device:	• Flexible soft bottom edge including wireless edge activator. • Break-away and self-repair function. • Photocells in side columns.
12	Manual activation :	by releasing the brake at ground level. Partly opening by means of the pre-stressed tension springs.
12	Motor and Hood Cover	GI 0.8mm thick

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 7410169333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd