**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

# NIHVA Sales Quotation

**IC-L Construction Consulting Pvt. Ltd**
B-6, Second Floor,
Heritage House "B" Wing,
Ramabai Ambedkar Rd.,
Pune 411 001.

**Date : 07.01.2020**
Quote NO : SQT.19.20.2336A
**Kind Attn : Mr. Vivek Shiroor**
Email Id : vivek.shiroor@iclconsulting.in
Contact No: **99 6051 2224**

**Project Name & Location:** Hyderabad, Telangana.

**Subject : Quotation for Dock Leveller.**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |

**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **Nihva Make Dock Leveller (6 Ton)** | 2000 | 2500 | 1 | 210,000 | 210,000 | 20,000 | 20,000 |
| 2 | **Nihva Make Dock Leveller (10 Ton)** | 2000 | 2500 | 1 | 235,000 | 235,000 | 20,000 | 20,000 |
| | | | | **Total** | | **445,000** | | **40,000** |
| | | | P&F Charges | 3% | | **13,350** | | |
| | | | **Total Without Taxes** | | | **458,350** | | **20,000** |
| | | | GST Extra @ 18% | 18% | | 82,503 | | 3,600 |
| | | | **Total With Taxes** | | | **540,853** | | **23,600** |
| | | | Transportation Charges | | | **In Client Scope** | | |
| | | | Unloading Charges @ Site | | | **In Client Scope** | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

| Sr .No. | Description | Specifications |
|---|---|---|
| 1 | **Capacity** | 6 Ton / 10 Ton |
| 2 | **Dock operation mode** | AC power pack hydraulically operated |
| 3 | **Lip operation mode** | Hydraulic |
| 4 | **Operation control** | Through panel |
| 5 | **Loading platform height from road** | 4 Ft |
| 6 | **Travel above & below dock level** | (+) 300 / (-) 150 mm |
| 7 | **Platform Size (W x L)** | 2000 mm x 2500 mm |
| 8 | **Lip size (W x L )** | 2000 x 400 mm |
| 9 | **Shut Height** | 480 mm |
| 10 | **Working length** | 2900 mm |
| 11 | **Overall length** | 2000mm x 2500mm + Lip Length (400mm ) |
| 2 | **Maximum slope can be achieved** | 0.1 |
| 3 | **Clear Pit dimensions (W x L x D)** | (W) 2050mm x (L) 2550 mm x (D) 485 mm |
| 4 | **Hydraulic power pack** | Standard |
| 5 | **Driver type** | Direct by electric Motor |
| 6 | **Motor Ratings** | 1 H.P Motor |
| 7 | **Pump design flow** | 2.5 LPM |
| 8 | **Pump pressure** | 120 bar Operating 200 bar Max. |
| 9 | **Safety valve set pressure** | 120 Kg/cm² |
| 10 | **Pump Type** | Gear |
| 11 | **Volume of oil receiver** | 7 Lit |
| 9 | **No Of Deck cylinder** | 2 No |
| 10 | **Lip Cylinder** | 1 No |
| 11 | **Dock Bumper** | 1 Pair |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain on 8551092333.**

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd