NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Rockman Industries Limited
503,D4 Saket District Centre,Rectangle 1,
New Delhi,,South Delhi, Saket, District Center
New Delhi - 110001, Delhi, India

Date : 03.02.2020
Quote NO : SQT.19.20.2399
Kind Attn : Mr. Anand Prakash
Email Id : apgaur@rockman.in
Contact No: 9971001378

Subject : Quotation for High Speed Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
Option 1 (ASSA ABLOY)								
1	**High Speed Door**	2000	2100	2	5,71,000	11,42,000	20,000	40,000
2	**High Speed Door**	2500	3600	1	6,06,000	6,06,000	20,000	20,000
3	**High Speed Door**	4000	4500	1	6,83,000	6,83,000	20,000	20,000
Option 2 (NIHVA Make)								
4	**HIGH SPEED PVC ROLL UP DOOR**	2000	2100	2	2,82,000	5,64,000	18,000	36,000
5	**HIGH SPEED PVC ROLL UP DOOR**	2500	3600	1	3,18,000	3,18,000	18,000	18,000
6	**HIGH SPEED PVC ROLL UP DOOR**	4000	4500	1	3,54,000	3,54,000	18,000	18,000
					Total	-		-
7	P&F Charges			3%	3% on Total			
Total Without Taxes					-		-	
GST Extra @ 18%				18%	-		-	
Total With Taxes					-		-	
8	Transportation Charges				**In Client Scope**			
9	Unloading Charges @ Site				**In Client Scope**			

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

High Speed Door RR300 + Alu (Assa Abloy)



Sr. No.	Description	Specification
1	Door type	RR300 Plus Alu
2	Description	Flexible High Performance Door, opening in vertical direction for interior use in wind-protected areas
3	Door curtain	Made of transparent PVC with fabric reinforcement stripes, ultramarine (similar to RAL 1021) (similar to RAL 3002).
4	Top roll	Made of anodized aluminum
5	Wind protection	wind tabs on the door curtain
6	Wind resistance	Class 1 (EN 12424).
7	Bottom profile	anodized aluminum
8	Drive unit	Hollow shaft gear motor
9	Protection	IP 55
10	Control system	Frequency converter control system MCC Vector Control, based on vector control including
11	Supply voltage	3L(N)PE/380/400/415/440/480V;50/60Hz
12	Safety devices	electrical safety contact edge, evaluation via integrated cable chain, door line photocell in
13	Manual activation	By releasing the brake at ground level. Depending on width/height ratio the door opens up
14	Opening / closing Speed	(open/close) up to max. 2,2/0,9 m/s,

HIGH SPEED PVC ROLL UP DOOR (NIHVA Make)

- Safe & for continous operations
- Self Supporting Construction with anti crash protection system for bottom profile
- Smooth & silent opening & closing
- Can be equipped with full vision PVC curtain
- Modular Interchaegable panels permit to replace worn & damged panels



Sr. No	Description	Specifications
1	Use	Internal Door
2	Speed	Inverter Motion system to adjust different speeds, with progressive control of acceleration & deceleration during braking
3	Opening speed	3 m/s
4	Closing speed	0.8 m/s
5	Control Panel	4 Push Button operated
6	Security Features	EN 13241-1 Standard
7	Resistance to wind load	EN12424 upto class 2
8	Curtain	Fabric Transparent PVC section
9	Guide Material	Aluminum
10	Hood Cover	GI
11	Motor Cover	GI
12	Operator & Control	German Make Motor
13	Connecting Voltage	220V , 1Ph , N
14	Open-Stop-Close Button	Standarad
15	Protection Category	IP 54 / IP 65
16	Power Consumption	0.75 kw Motor
17	Emergency Off Button	Standard
18	Closing Zone Monitoring	Optical Safety edge
19	External Route Monitoring	Photocell
20	Emergency Opening	Crank Handle

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Sunny on 8551035333**

With Best Regards
Vivek
8530370333
For NIHVA Technologies Pvt Ltd