NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Azad Rolling Shutter and Construction
Mohan Cinema Road, Opp. J. P. Market
Kota - 324 006 (RAJASTHAN)

Date : 20.01.2021
Quote NO : SQT.20.21.2955
Kind Attn : Mohammed Zuber
Email Id : azadrollingshutter@yahoo.co.in
Contact No: 9828137864/9828384287

Project, Location : Kota, Rajasthan

Subject : Quotation for NIHVA MAKE High Speed Doors

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**NIHVA Make High Speed Door**	3450	3500	2	320,000	640,000	20,000	40,000
	Total			**2**		**640,000**		**40,000**
2	P&F Charges			3%		19,200		
	Total Without Taxes					659,200		40,000
	GST Extra @ 18%			18%		118,656.00		7,200
	Total With Taxes					**777,856**		**47,200**
3	Transportation Charges					**Extra at atcual**		
4	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

HSD - NIHVA MAKE

- Safe & for continous operations
- Self Supporting Construction with anti crash protection system for bottom profile
- Smooth & silent opening & closing

Sr. No	Description	Specifications
1	Use	Internal Door
2	Speed	Inverter Motion system to adjust different speeds, with progressive control of acceleration & deceleration during braking
3	Opening speed	0.8 m/sec
4	Closing speed	upto 1.5 m/sec
5	Control Panel	4 Push Button operated
6	Security Features	EN 13241-1 Standard
7	Resistance to wind load	EN12424 upto class 1
8	Curtain	Fabric Transparent PVC section
9	PVC Fabric Standard	EN 12641-2
10	Guide Material	Aluminum
11	Hood Cover	GI-0.9 mm Thinkness
12	Motor Cover	GI
13	Operator & Control	German Make Motor
14	Connecting Voltage	230V , 1Ph , N
15	Open-Stop-Close Button	Standarad
16	Protection Category	IP 54 / IP 65
17	Power Consumption	0.75 kw Motor
18	Emergency Off Button	Standard
19	Closing Zone Monitoring	Optical Safety edge
20	External Route Monitoring	Photocell
21	Emergency Opening	Crank Handle
22	Magnetic Loop Detector	Including - Protection category IP-65

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10 - 12 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Bhavin Jain on 8551092333** For any further Clarification /Information in this Concern.

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd