**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**Reliable Constrotech Enterprises**
Thane, Maharashtra,
400602, India

**Date : 14.08.2019**
**Quote NO : SQT/19-20/1931**
**Kind Attn : Mr. Rohit Kamble**
**Email Id : rohit.kamble@reliableconstrotech.com**
**Contact No: 9766111625**

**Subject : Quotation for Sectional Door and Rolling Shutter.(Project -TATA CUMMINS PRIVATE LIMITED PHALTAN)**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |

**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | Sectional Door | 3000 | 5000 | 7 | 340,000 | 2,380,000 | 20,000 | 140,000 |
| 2 | Motorized Rolling Shutter | 4000 | 5000 | 4 | 133,000 | 532,000 | 20,000 | 80,000 |
| | | | **Total** | | | **2,912,000** | | **220,000** |
| 3 | P&F Charges | | | 3% | | 87,360 | | |
| | **Total Without Taxes** | | | | | 2,999,360 | | 220,000 |
| | GST Extra @ 18% | | | 18% | | 539,884.80 | | 39,600 |
| | **Total With Taxes** | | | | | **3,539,245** | | **259,600** |
| 4 | Transportation Charges | | | | | In Client Scope | | |
| 5 | Unloading Charges @ Site | | | | | In Client Scope | | |
| | Optional Accesaries | | | | | | | |
| 6 | **Grill - Per Sq.Meter** | | | 1 | 1,500 | 1,500 | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

| Sr .No. | Specification | Crawford - NIHVA Assaabloy | |
|---|---|---|---|
| 1 | Door type | 1042P | |
| 2 | Clear Opening dimension | (W)3000 x (H) 5000 mm | |
| 3 | Opening Direction | 90 Degree | |
| 4 | Type of Mounting | High Lift | |
| 5 | Door produced Based on which certificatio | Doors produced according to ISO 9000 or ISO 14000 certified | |
| 6 | Opening/Closing Speed | 0.25 m/s | |
| 7 | **Door Material** | GI Steel with PUF inside | |
| 8 | Panel Thickness | 42mm | |
| 9 | Panel colour | RAL 9002 Powder coated | |
| 10 | External surface of the panel | diamond grid design with a glossy finish at the section joints. | |
| 11 | inside surface of the panel | Monolithic surface on the inside of the door | |
| 12 | Broken cold bridge | Section joints with broken cold bridges | |
| 13 | Door sealent | All door sealants made of EPDM rubber. | |
| 14 | All Panel height | All panels should be 545mm high | |
| 15 | Panel Inside insulation metrial | Insulation material to be CFC free polyuretane foam. | |
| 16 | Panel Flame Retardent standrad | Flame retardant polyurethane foam according DIN4102-class B2. | |
| 17 | Steel component Material | All steel components to be electro galvanized | |
| 18 | Hinge Material | Glass fibre reinforced Polyamide | |
| 19 | Panel Thickness | 42 mm | |
| 20 | Spring Material surface finish | Powder coated | |
| 21 | Water Penetration | EN 12425 | class 3 |
| 22 | Air Permealibity | EN12426 | class 2 |
| 23 | Wind Load | EN21424 | class 3 |
| 24 | Thermal Transittance | EN 12428 1.10W /m2K | |
| 25 | Bottom sealing | Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber | |
| 26 | Door saftey device 1 | Doors equiped with spring break device | |
| 27 | Door saftey device 2 | Door equiped with pneumatic safety edge | |
| 28 | Door saftey 3 | Having hinges flush with the inside door surface is a safety feature that eliminates the risk of things or people getting caught by parts protuding from a moving door | |
| 29 | Incase of Power failuer | One can operate the Door manually | |
| 30 | Operator power conumption | Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W | |
| 31 | Drive Unit & Mounting Type | Single phase 230V direct drive on shaft | |
| 32 | Emergency Operation | by Disengagement rope manual | |
| 33 | Operating Switch | Up/Down Keypad + stopbutton | |
| 34 | Environmental Green Product Declaration Certification | as per ISO 14025 and EN 15804 | |

| Sr .No. | Specification | Motorized Rolling Shutter |
|---|---|---|
| 1 | Description: | Motorised Rolling Shutter with MS Laths with thickness of 1 mm. |
| 2 | Mounting Location area | Inside area / Outside area |
| 3 | Mounting Surface | Side Brackets: Optional = On Concrete /Steel & Side |
| 4 | Curtain Panel | The panel made of 1.0mm thick MS. |
| 5 | Curtain panel size | 75mm wide |
| 6 | Curtain Profile | Curved |
| 7 | Bottom Profile | M. S. Plate 100 mm x 2.5 mm thick with angle stiffener |
| 8 | Side Guide Profile | M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension) |
| 9 | Roller Shaft | M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h |
| 10 | Side Brackets | MS Plate 3 mm to 10 mm thick, as per the opening dimension. |
| 11 | Hood Cover | Made of GI Sheet Thickness 1.2 mm GF mm with 25x25x3mm angle stiffener |
| 12 | Surface finish | PU paint or Powder coated |
| 13 | Drive Unit & Mounting Type | Electric Motor - Direct Mounting - Sprocket chain arrangement – IP54 Protection |
| 14 | Wind Pressure | 1oo km/hr |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

Please feel free to Contact **Mr.Ravindra Kharat on 7410169333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd