NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/19-20/1801 **Date : 10.07.2019**

Rajendra Mittal Construction Company Pvt. Ltd.
Redg. Office: 210-211, OPTUS Corporate Suites,
Vasundhara Nagar, Bhiwadi- 301019
Distt. Alwar, Rajasthan .

Kind Attn: Mr. Rajendra Mittal
Email ID: mittal_construction@yahoo.co.in
Contact No: 9887069408

Project Name And Location : Alwar, Rajasthan

Subject : Quotation for Motorized Sliding Gate.

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**AUTOMATIC SINGLE LEAF SLIDING GATE** **(Supply + Installation)**				
	Sliding Gate - (W) 8000 mm X (H) 1800 mm **• For Post- 100 x 100 x 4mm MS SQ. TUBE** **• Outer Frame- 100 x 100 x 4mm MS SQ. TUBE** **• Inner Frame - 50x50x3mm MS SQ. TUBE** **•Gap Between Tubes - 100 MM**				
1	**Size : (W) 8000 mm X (H) 1800 mm**	1	No	506,000	**506,000**
B	**AUTOMATIC SINGLE LEAF SLIDING GATE** **(Supply + Installation)**				
	Sliding Gate - (W) 7000 mm X (H) 1800 mm **• For Post- 100 x 100 x 4mm MS SQ. TUBE** **• Outer Frame- 100 x 100 x 4mm MS SQ. TUBE** **• Inner Frame - 50x50x3mm MS SQ. TUBE** **•Gap Between Tubes - 100 MM**				
1	**Size : (W) 7000 mm X (H) 1800 mm**	1	No	492,000	**492,000**
C	**AUTOMATIC SINGLE LEAF SLIDING GATE** **(Supply + Installation)**				
	Sliding Gate - (W) 6000 mm X (H) 1800 mm **• For Post- 100 x 100 x 4mm MS SQ. TUBE** **• Outer Frame- 100 x 100 x 4mm MS SQ. TUBE** **• Inner Frame - 50x50x3mm MS SQ. TUBE** **•Gap Between Tubes - 100 MM**				
1	**Size : (W) 6000 mm X (H) 1800 mm**	1	No	440,000	**440,000**
D	**AUTOMATIC SINGLE LEAF SLIDING GATE** **(Supply + Installation)**				
	Sliding Gate - (W) 5000 mm X (H) 1800 mm **• For Post- 100 x 100 x 4mm MS SQ. TUBE** **• Outer Frame- 100 x 100 x 4mm MS SQ. TUBE** **• Inner Frame - 50x50x3mm MS SQ. TUBE** **•Gap Between Tubes - 100 MM**				
1	**Size : (W) 5000 mm X (H) 1800 mm**	1	No	404,000	**404,000**

GST Pune	**27AAECN0437H1ZM**	**Grand Total**	**1,842,000**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@ 3% of Total supply value
3	**Freight Notes**	:	Extra as applicable
4	**Delivery**	:	5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST Extra 18%
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

If there is any query please feel free to contact Mr. Arjun Patil on 8551096333.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd