NIHVA Technologies Pvt. Ltd.

BILL OF MATERIAL

Format No.: NIHVA-DEG-F-06	
Revision No.:00	
Revision Date :	
Date of Origin :25-01-2025	
Project Number:	
Customer : TATA CUMMINS	
Width (mm)	**4500**
Height (mm)	**5000**
Quantity	**1**

PRODUCT -GEAR OPERATED ROLLING SHUTTER (MANUALLY ROLLING SHUTTER)

SR NO	PART NAME	SEGMENT	MATERIAL	LENGTH (MM)	QUANTITY FOR 1	WEIGHT IN Kg	UNIT	REMARK
1	GI SLAT 1 NIHVA STD	Mechanical	1 MM	4700	85	297	nos	
2	Guide type - T Guide	Standard	150 X 3.0 MM	5150	2	29	nos	
3	Bottom	Standard	100 x 2 mm (MS)	4700	1	5	nos	
4	RUBBER AT BOTTOM	Standard	RUBBER		5		metre	
5	BOTTOM ISA(ANGLE)	Standard	30x30x3mm (MS)	4480	2	13	nos	
6	MANUAL CHAIN	Standard			8		metre	Considered 0.5m extra
7	HOOD COVER	Mechanical	MS-GI-0.9mm*1000	5000	1	36	nos	
8	MOTOR COVER	Mechanical	MS-GI-0.9mm*400	1150	1		nos	
9	PAINT	Standard	POWDER COATED		2		Litre	
10	MOTOR MOUNTING BRACKET	Mechanical	MS		2	10	nos	
11	SHAFT	Mechanical	MS	4740	1	36	nos	Dia 140 mm
12	NUT & BOLT	Standard	MS		30		nos	
13	SADLE	Standard			10		nos	
14	SADLE SCEW	Standard			20		nos	
15	CIRCLIP FOR SHAFT	Standard			2		nos	
16	M8 SELF THREADING SCREW	Standard			20		nos	
17	RAWAL PLUG FOR SADLE	Standard			30		nos	
18	STARTING STRIP (KAPATI PATTI)	Standard	according		0		0	
19	GEAR OPERATED MECHANISUM	Electrical			1		nos	