NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Trident India
E-212 Kitchlu Nagar,
Ludhiana - 141001

Date : 22.03.2021
Quote NO : SQT.20.21.3114
Kind Attn : Deepika Garg
Email Id : deepikagarg@tridentindia.com
Contact No: 9755095228

Subject : Quotation for Nihva Make High Speed Rapid Roll up Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**High Speed Rapid Roll up Door**	2800	3000	2	327,000	654,000	20,000	40,000
	Total			**2**		**654,000**		**40,000**
	P&F Charges			3%		19,620		
	Total Without Taxes					673,620		40,000
	GST Extra @ 18%			18%		121,252		7,200
	Total With Taxes					**794,872**		**47,200**
	Transportation Charges					**Extra at atcual**		
	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

High Speed Door



- Safe & for continous operations
- Self Supporting Construction with anti crash protection system for bottom profile
- Smooth & silent opening & closing
- Can be equipped with full vision PVC curtain
- Modular Interchaegable panels permit to replace worn & damged panels
- Advance and robust control devices

Sr. No	Description	Specifications
1	Use	Internal Door
2	Speed	Inverter Motion system to adjust different speeds, with progressive control of acceleration & deceleration during braking
3	Security Features	EN 13241-1
3	Opening Speed up to	Opening 3.0 m/s.
	Closing Speed	0.8 m/s.
4	Control Panel	4 Push Button operated
5	Resistance to wind load	EN 12424 upto Class 2
	Curtain stabilisation / Wind load	Aluminium anodized windbars
6	Curtain	Fabric -0.9 to 1.5 mm Transparent PVC section -2.0 mm
7	Curtain colour	Standard blue RAL 5010
7	Guide Material / Surface	Aluminium anodized
8	Hood Cover	GI
9	Motor Cover	GI
10	Operator & Control	German Make Motor
11	Connecting Voltage	220 V ~ / 50 - 60 Hz - 1 PH , N
12	Open-Stop-Close Button	Standarad
13	Protection Category (Operator / Control)	IP 54 / IP 65
14	Power Consumption	0.75 kw Motor
15	Emergency Off Button	Standard
16	Closing Zone Monitoring	Optical Safety edge
17	External Route Monitoring	Photocell
18	Emergency Opening	Crank Handle

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10 -12 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Shrikant Mirkute on 8551098333**

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd