QTN No:- SQT/19-20/1853R

Dated : 26.07.2019

Kind Attn:- Mr. Ajay Mahade

Client Name:- **Rohan Builders (India) Pvt. Ltd.**

Address :- 1 Modibag,Commercial Building,Pune - 411 001
Ganeshkhind Road, Shivaji Nagar,
Pune – 411 016 , Ph : - 020-7101 7280

Email Id:- inquiry.ho@rohanbuilders.com

Contact Detail: 020-7101 7280

Dear Sir,

This is with reference to your requirement of Access Cover , we are pleased to quote, competitive rates for ***NIHVA Technologies Pvt. Ltd*** *authorized associated partner of* ***ACO Systems & Solutions (Germany).*** *We hope you find our quotation in line with your requirement. Looking forward for offering better solutions in drainage system.*

PROJECT : Dawtlyer

Sr. no	Description of Products	Total Qty.	Unit	Price Per Nos	Amount
	V 200 - Option with D 400 /E600 Load Class				
1	**DRAIN IN GROUND FLOOR DRIVE WAY : Polymer Concrete Channel body V200 (200 mm wide and depth 265- 365 mm); DIN EN 1433 with boltless drainlock®, V-profile, zero water absorption, integrated edge protection in galvanised steel, with ACO DRAIN safety groove (SF), tongue and groove joints, with built-in slopes; With integrated lip labyrinth sealing for liquid-tight connection to ground line, with lateral pre-shapes for corner-, T- and cross connections, universal front wall, with edge protection; grating made up of ductile iron material suitable for the polymer concrete drain channel, load class C250or D 400 as per DIN EN 1433; depth of the drain as per design, Internal width: 200mm**	50	Rmt	22,715	1,135,750
	V200 - Option 2 with C250 Load Class				
2	**DRAIN GROUND FLOOR DRIVE WAY : Polymer Concrete Channel body V300 (300 mm wide and depth 385- 485 mm); DIN EN 1433 with boltless drainlock®, V-profile, zero water absorption, integrated edge protection in galvanised steel, with ACO DRAIN safety groove (SF), tongue and groove joints, with built-in slopes; With integrated lip labyrinth sealing for liquid-tight connection to ground line, with lateral pre-shapes for corner-, T- and cross connections, universal front wall, with edge protection; grating made up of ductile iron material suitable for the polymer concrete drain channel, load class C250or D 400 as per DIN EN 1433; depth of the drain as per design, Internal width: 300mm**	50	Rmt	18,900	945,000
	V300 - Option 2 with D400 / E600 Load Class				
3	**DRAIN GROUND FLOOR DRIVE WAY : Polymer Concrete Channel body V300 (300 mm wide and depth 385- 485 mm); DIN EN 1433 with boltless drainlock®, V-profile, zero water absorption, integrated edge protection in galvanised steel, with ACO DRAIN safety groove (SF), tongue and groove joints, with built-in slopes; With integrated lip labyrinth sealing for liquid-tight connection to ground line, with lateral pre-shapes for corner-, T- and cross connections, universal front wall, with edge protection; grating made up of ductile iron material suitable for the polymer concrete drain channel, load class C250or D 400 as per DIN EN 1433; depth of the drain as per design, Internal width: 300mm**	75	Rmt	47,300	3,547,500

V300 - Option 2 with C250 Load Class					
4	**DRAIN GROUND FLOOR DRIVE WAY : Polymer Concrete Channel body V300 (300 mm wide and depth 385- 485 mm); DIN EN 1433 with boltless drainlock®, V-profile, zero water absorption, integrated edge protection in galvanised steel, with ACO DRAIN safety groove (SF), tongue and groove joints, with built-in slopes; With integrated lip labyrinth sealing for liquid-tight connection to ground line, with lateral pre-shapes for corner-, T- and cross connections, universal front wall, with edge protection; grating made up of ductile iron material suitable for the polymer concrete drain channel, load class C250or D 400 as per DIN EN 1433; depth of the drain as per design, Internal width: 300mm**	75	Rmt	42,133	3,159,975
			Total (Rs.)		**8,788,225**

Note : The Final Production Drawings Approval is compulsory before processing of Final Order.

Terms & Conditions :-

1) Transportation will be extra at actual
2) Delivery : 11 - 12 Weeks from date of confirmed Purchase Order & advance payment.
3) Taxes : GST 18% Extra
4) Validity : 30 Days from Date of Quotation
5) Installation is in your scope. Our Techncian will only guide the installation on site.
6) Unloading of Material at site is in client Scope.
7) Payment Term :- Advance 100% of supply along with confirmed P.O.

For any further Query please Contact **Mr.Bhavin Jain** on 8551092333.

With Best Regards

Ulka Auti.
7219206333
For NIHVA Technologies Pvt Ltd