Sales Quotation

Quotation No - SQT/18-19/1295DR **Date : 16-08-2019**

Ratnarup Projects Pvt. Ltd.,
Baner
Pune

Kind Attn: Mr. Ajit Jadhav
Email: ajit@ratnarupprojects.com
Contact: 9623589393

Project Name And Location : Stihl, Chakan, M.I.D.C., Phase-3 site.

Subject : Quotation for Dock Shelter.

Dear Sir
Thank you for the opportunity and trust shown on "NIHVA", your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication. please find below our best offer.

Commercial Offer

Sr. No	Description	Qty.	Unit	Rate In INR	Net Amount INR
A	**NIHVA Rectractable Dock Shelter (100% Imported with all components – made in Europe)**				
1	**Size : (W) 3250 mm x (L) 4000 mm** **(Supply + Installation)**	6	No	234,000	1,404,000
	Optional Features:				
1	Angle Cushion	1	No	Inclusive in Price.	
2	Rain Water Evacuation Channel	1	No	Inclusive in Price.	
3	Laminated Curtain	1	No	NA	NA

B) **Technical Specification**

Sr. No	Specification	NIHVA Assaabloy Rectractable Dock Shelter
1	Door type	Dock Shelter DS6060A
2	Clear Opening dimension	(W) 3250 mm x (L) 4000 mm
3	Curtain colour	Black
4	Parking Guides	White, Yellow
5	Wall Fixings	Concrete, Sandwich light Concrete, Load house cavity, insulated panel
6	Top & Side Curtaiins	Double Layer High Quality Polyester
7	Thickness	3.0 mm
8	Weight	Approx 3400 g/m2
9	Continous Roof Cover	One layer high quality Polyester
10	Thickness	0.5 mm
11	Weight	Approx 680 g/m2

GST Pune:	27AAECN0437H1ZM

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2. Any civil / masonry / structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provide structure drawing only if required
5. Existing / Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@ 3 % of total supply value
3	**Freight Notes**	:	Extra as applicable
4	**Delivery**	:	8 -9 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST @ 18% Extra
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Swapnil Kulat** on 7219207333 For any further Clarification /Information in this Concern.

With Best Regards

Ulka Auti.
7219206333
For NIHVA Technologies Pvt Ltd