NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/19-20/1806R **Date :30-07-2019**

INDOSPACE
One Indiabulls Centre, 11th Floor, Tower 2A,
Senapati Bapat Marg, Elphinstone Road,
Mumbai - 400013, India.

Kind Attn: Mr. Tushar Dhande
Email: tushar.dhande@indospace.in
Contact No : 8879311890

Project Name And Location :Chakan.

Subject : Quotation for Rolling Shutter, High Speed Door, Dock Leveller and Dock Shelter.

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr.No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Motorized Rolling Shutter** **Technical Specifications:** **• GI Slat : 1.0 mm Thick** **• Profile : Curved Type Profile with heavy duty Shaft** **• Guide : 2.5 mm Thick MS Guide** **• Hood Cover & Motor Cover : 0.9 mm Thick GI material** **• Indirect Drive** **• With Painting** **(Supply + Installation)**				
1	Size (W) 5000 mm x (H) 5000 mm	6	No	171,000	1,026,000
2	Size (W) 3600 mm x (H) 5000 mm	3	No	136,000	408,000
3	Size (W) 3600 mm x (H) 4500 mm	1	No	125,000	125,000
4	Size (W) 2400 mm x (H) 3000 mm	2	No	79,000	158,000
				Total	1,717,000
B	**Gear Operated Rolling Shutter** **Technical Specifications:** **• GI Slat : 1.0 mm Thick** **• Profile : Curved Type Profile with heavy duty Shaft** **• Guide : 3 mm Thick MS Guide** **• Hood Cover :0.9 mm Thick GI material** **• Gear Assembly** **• With Painting** **(Supply + Installation)**				
1	Size (W) 2000 mm x (H) 3000 mm	3	No	77,000	231,000
2	Size (W) 3000 mm x (H) 3000 mm	3	No	91,000	273,000
3	Size (W) 2251 mm x (H) 2415 mm	1	No	72,000	72,000
4	Size (W) 2000 mm x (H) 2200 mm	1	No	67,000	67,000
				Total	643,000

High Speed Door -(Option 1)					
C	**Albany Make Rapid Roll Up Door RR300+AL (Wind Class -1)** **(100% Imported with all components – made in Germany)** **(Supply + Installation)**				
Door panel:	Transparent PVC with Red (RAL 3002) reinforcement stripes.				
Barrel:	Aluminium, anodized with shafts made of galvanized steel				
Wind Reinforcement:	Door Panel wind tabs for improved wind resistance				
Side Frames:	Aluminium profiles, anodised				
Drive Unit:	Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)				
Self-opening:	Standard - the door can be opened partially up to 1,8 m by releasing the brake manually.				
Bottom beam:	Anodized extruded aluminium.				
Control system:	MCC Vector Control - frequency converter control system for a dynamic, smooth door movement, located close to the drive unit Max. Opening Speed 2.2m/s Max. Closing Speed 0.9 m/s				
Safety features:	Safety edge, safety photocell (Transmitter/Receiver) inside side columns				
1	**Size: (W) 4000 mm X (H) 4500 mm**	3	Nos.	656,000	**1,968,000**
2	**Size: (W) 3600 mm X (H) 4500 mm**	5	Nos.	649,000	**3,245,000**
3	**Size: (W)2500 mm X (H) 2500 mm**	1	Nos.	572,000	**572,000**
	Total				**5,785,000**
High Speed Door -(Option 2)					
D	**Albany Make Rapid Roll Up Door RR392 (Wind Class - 2)** **(100% Imported with all components – made in Germany)** **(Supply + Installation)**				
Basic Equipment :	High-Speed Roller Door with transparent curtain and blue (similar RAL 5002) reinforcement stripes, optional red (similar RAL 3002). Door with curtain tension.				
Drive Unit :	Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)				
Control system :	MCC Vector Control - frequency converter control system for opening/closing speed up to 2,2 / 0,9 m/s				
Power supply :	3/(N)/PE/230/400/415 v; 50 Hz				
Safety :	Safety contact edge, Safety photocell transmitter / receiver inside side columns.				
	Top Cover Inclusive				
	Motor cover Inclusive				
1	**Size : (W) 4000 mm x (H) 4500 mm**	3	No	779,000	2,337,000
2	**Size : (W) 3600 mm x (H) 4500 mm**	5	No	772,000	3,860,000
3	**Size : (W) 2500 mm x (H)2500 mm**	1	No	691,000	691,000
				Total	**6,888,000**

E	**Assa Abloy Make Dock Shelter - DS6070E** **Inflatable Dock Shelter (100% Imported products from Europe)**				
1	Size : (W)3600 mm x (H)3755 mm Supply + Installation	4	Nos.	452,000	1,808,000
				Total	**1,808,000**
F	**Dock Leveler (NIHVA Make)** **2 cylinder for Deck & 1 cylinder for LIP Operator by Standard Control Panel (Deck Up / Down / Lip Up / Down)** **Rubber Bumpers.** **(Supply + Installation)**				
1	**Dock Leveler Capacity 6 Ton** Size : (W) 2000 mm X (L) 2500 mm X (H) 480mm	3	No	**215,000**	645,000
2	**Dock Leveler Capacity 9 Ton** Size : (W) 2000 mm X (L) 2500 mm X (H) 480mm	1	No	**225,000**	225,000
3	**Transportation**	4	No	**15,000**	60,000
				Total	930,000

Dock Leveler Image & Technical Specifications







Sr. No.	Description	Specifications
1	Capacity	9 Ton
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Through panel
5	Loading platform height from road	1250mm
6	Travel above & below dock level	(+) 300 / (-) 250 mm
7	Platform Size (W x L)	2000 mm x 2500 mm
8	Lip size (W x L)	2000 x 400 mm
9	Shut Height	480 mm
10	Working length	2900 mm
11	Maximum slope can be achieved	10%
12	Clear Pit dimensions (W x L x D)	(W) 2050mm x (L) 2500 mm x (D) 485 mm
13	Hydraulic power pack	Standard
14	Driver type	Direct by electric Motor
15	Motor Ratings	1 H.P Crompton Greaves Make
16	Pump design flow	2.5 LPM
17	Pump pressure	120 bar Operating 200 bar Max.
18	Safety valve set pressure	120 Kg/cm²
19	Pump Type	Gear
20	Volume of oil receiver	7 Lit
21	No Of Deck cylinder	2 No
22	Lip Cylinder	1 No
23	Dock Bumper	Included

General Prerequisites Required at Site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places.
3 Provide electrical cables near to the installation machinery
4 Fork lift/crane to be provided if required .
5 Scaffolding require for Installation it is in client scope.

Limit of Supply

1 Provide place to store the material to be installed .
2 Be responsible for the safe custody of all material.
3 Provide place to safely store all the tools of installation
4 Provide change & rest room for the workers.

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel.

Client Scope

1 Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2 Any civil / masonry/structural work required to support are in client scope
3 All structure support is in client scope
4 NIHVA Will provided structure drawing only if required
5 Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@ 3% of Total supply value
3	**Freight Notes**	:	Extra as applicable
4	**Delivery**	:	9-10 Weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Taxes**	:	GST Extra @ 18%
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil** on **8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd