~~Ref~~ Given comments are not fully incorporated.

Remove old position lines from drawing

Refer general comments given on drawing no A-10-101

A B C D

6500 6800 9250

1 2 3 4 5

5400 3250 2275 3250 3175

20A ROLLING SHUTTER ISOLATOR

CONTROL PANEL

20A ROLLING SHUTTER ISOLATOR

20A ROLLING SHUTTER ISOLATOR

150MM CABLE TRAY DROPPED FROM FIRST FLOOR
REFER DRAWING NO:- DIAL-LT-D-UTL-E-14-302 (TYP.)

RS-VTPN-DB

150MM CABLE TRAY DROPPED FROM FIRST FLOOR
REFER DRAWING NO:- DIAL-LT-D-UTL-E-14-302 (TYP.)

32A IND

CFT PARKING

UP

CONTROL PANEL

20A ROLLING SHUTTER ISOLATOR

There is no wall at this location. Re-locate Control Panel at column face

CONTROL PANEL

20A ROLLING SHUTTER ISOLATOR

There is no wall at this location. Relocate Control panel at column face.

CONTROL PANEL

20A ROLLING SHUTTER ISOLATOR


Need to be shifted for clearance from door


DN

UP


Remove lines from drawing. Show current position of Roll-up fabric on plan

- Show roll-up fabric in plan with proper numbering & dimensions
- Submit this drawing also with drawing format & number.






SECTION A-A (Scale 1:50)
Hole pattern for header box attachment




SECTION B-B
Door leaf is not shown for clarification
Scale 1:50




DETAIL C, SCALE (1:10)

ANCHOR POSITION FROM COLUMN



SECTION C-C
Open door
Scale 1:50

Check Scale



SECTION C-C
Closed door
Scale 1:50


Check Scale

Correct the sequence


Provide both/bottom detail

Cable detail to be mentioned in drawing


Mention Vendors name



Force by differential pressure transferred to guide rail at each intermediate position.
F=4.7 kN




Load on header box attachment (each screw), due to wind load and door weight



DETAIL B, SCALE (1:10)

GUIDE RAIL MOUNTING DETAILS

Why scale is made down from 1:5?



DETAIL A, SCALE (1:10)

HEADER BOX MOUNTING DETAILS

Cross check the detail scale. Make it 1:5

NOT INCLUDED IN DOOR SUPPLY:

1. Design and supply of all door supporting structural components.
2. Design and supply of all closure between door and adjacent steel.
3. Door jambs adjustable for overall door width and true to plumb.
4. Paint job after completed door installation.
5. Any frameworks being provided by ASSA ABLOY will be clearly indicated as "by ASSA ABLOY".

REQUIREMENTS ON BUILDING:

6. Door head support must be straight within 1/600 of span in the in/out direction and free from protrusions of any kind.
7. For a single door leaf, door head support should be horizontal and straight within 1/600 of span at distributed full door load.
8. Door side jambs must be smooth, straight and parallel, out of plumb must not exceed 2mm/m (total deviation at full length 5 mm) in any direction.
9. Any footings at bottom of jamb columns must not interfere with installation of guide rails at floor level.
10. At time of installation, finished floor, free from obstructions, out to a distance of 2 m on each side of door centreline must be available.
11. Header box must be accessible from both sides during installation.

DOOR PROPERTIES:

12. The door is designed to withstand a differential pressure of 1.15kPa x 1.5 FOS.
15. Guide rails, top- and intermediate beams in extruded aluminium with natural finish.
16. Color of header box: BLACK (NCS 9000-N, RAL 9005)
15. Color of door fabric: Color code of door fabric:Grey RAL 7004 (7072/ D3171) (Approved by DIAL)
16. Metal trim: motor side
17. Hand crank for manual operation.

ELECTRICAL:

18. One main control panel provided of PLC type.
19. Audible and visual alarm
20. Back-up power switch
21. Safety edge
22. Approx. size of main control panel: WxHxD (500mm x 600mmx250 mm),
23. Power: 2.7kW
24. Nom. current: 6.4A
25. (max. allowed voltage drop at start: 5%)
26. Power supply required: 3 Phase, 415 V +/-10%, 50 Hz +/- 3%
27. Cable tray size: 50mm (H) x 100mm (W)
28. Conduiting and cabling from motor to control panel is in vendor scope.

BELT HOIST UNITS:

SK 873.1-100L/4 Z dual brake


L&T Construction Buildings & Factories

A	APPROVED. PROCEED FOR MANUFACTURE/ CONSTRUCTION.
B	✓ APPROVED WITH COMMENTS. PROCEED TO MANUFACTURE/ CONSTRUCTION SUBJECT TO COMPLIANCE OF ALL COMMENTS AND RESUBMIT THE DOCUMENTS FOR LEVEL A APPROVAL.
C	RESUBMIT AFTER INCORPORATION OF ALL COMMENTS FOR REVIEW.
D	REJECTED. MAKE A RESUBMISSION ALTOGETHER FOR REVIEW.

REVIEW OF THIS DOCUMENT IS ONLY TO CHECK COMPATIBILITY WITH BASIC DESIGN CONCEPT. THIS DOES NOT ABSOLVE THE SUB-CONTRACTOR/ MANUFACTURER FROM RESPONSIBILITY TO MEET THE REQUIREMENT AS PER SPECIFICATIONS, CODES & STANDARDS, STATUTORY RULES & REGULATIONS, AS EXISTING OR AS MAY BE AMENDED FROM TIME TO TIME.

CHECKED BY: [signature]
LETTER REF:

VERIFIED BY:
DESIGNATION: HEAD ARCHITECT
DATE:
SIGNATURE:



KEY PLAN (NOT TO SCALE)

NOTE:
1. 340 MM RCC COLUMN REQUIRED FOR GUIDE MOUNTING.
IF RCC COLUMN NOT AVAILABLE THEN WE WILL REQUIRE MS STRUCTURE FOR THE SAME.

- All dimensions / sizes mentioned in shop drawings to be verified by vendor at site, prior to proceeding for production

REFERENCE DRAWING :

DIAL-LT-D-UTL-A-20-300 : ARFF4 FIRE STATION ELEVATIONS
DIAL-LT-D-UTL-A-20-301 : ARFF4 FIRE STATION ELEVATIONS
DIAL-LT-D-UTL-A-10-300 : ARFF4 FIRE STATION GROUND FLOOR PLAN

- All material & finishes shown in shop drawings are subject to MAS/ sample approved by DIAL.
- Previous comments are not fully incorporated.
- Please submit the final shop drawings to DIAL for approval.
- Details are not as per scale. Please correct.

C	Revised, issued for approval.	18.11.2021	18.11.2021	18.11.2021
B	Revised, issued for approval.	G.L.P	G.L.P	A.K.
A	Issued for approval	15.11.2021	15.11.2021	15.11.2021
		G.L.P	G.L.P	A.K.
		30.10.2021	30.10.2021	30.10.2021
		G.L.P	G.L.P	A.K.
REVNO.	DESCRIPTION	DESIGNED	DRAWN	CHECKED

REVISIONS

CHECKED BY	SIGN	DATE	CHECKED BY	SIGN	DATE	CHECKED BY	SIGN	DATE
ARCHITECTURE			HVAC			CIC		
CIVIL & STRUCTURAL			FPS			GEOTECH.		
ELECTRICAL			PIPING			AIRPORT SYSTEMS		
ELV SYSTEM			PHE			INTERFACE		

DELHI INDIRA GANDHI INTERNATIONAL AIRPORT — GMR — L&T Construction

DELHI INTERNATIONAL AIRPORT LIMITED

PROJECT: NEW GMR INTERNATIONAL AIRPORT PHASE-3A DEVELOPMENT WORKS

VIEW :

CONCEPT :

PROJECT CONSULTANT: Engineering Design and Research Center (EDRC), L&T Construction

DETAILED AND SUPPLIED BY: MIRA TECHNOLOGIES PVT LTD

JOB NO.

JOB No :	NAME	SIGN	DATE
DSGN	G.L.P		02.10.2021
DRWN	G.L.P		02.10.2021
CHKD	A.K.		02.10.2021
APPD	V.T.		02.10.2021

TITLE:
SHOP DRAWING
Building: ARFF4
ARFF4 MEGADOOR
8760 X 5400 (RS7)

SCALE: 1:50

DRAWING No. DIAL-LT-Q-UTL-A-10-101 SHEET


PROJECTION: FIRST ANGLE


SIZE: A3

REV: B

RELEASED FOR: ☐ PRELIMINARY ☐ TENDER ☐ INFORMATION ☑ APPROVAL ☐ CONSTRUCTION

Refer general comments given on drawing no. A-10-101





SECTION C-C
Open door
Scale 1:50

SECTION C-C
Closed door
Scale 1:50

NOT INCLUDED IN DOOR SUPPLY:

1. Design and supply of all door supporting structural components.
2. Design and supply of all closure between door and adjacent steel.
3. Door jambs adjustable for overall door width and true to plumb.
4. Paint job after completed door installation.
5. Any frameworks being provided by ASSA ABLOY will be clearly indicated as "by ASSA ABLOY".

REQUIREMENTS ON BUILDING:

6. Door head support must be straight within 1/600 of span in the in/out direction and free from protrusions of any kind.
7. For a single door leaf, door head support should be horizontal and straight within 1/600 of span at distributed full door load.
8. Door side jambs must be smooth, straight and parallel, out of plumb must not exceed 2mm/m (total deviation at full length 5 mm) in any direction.
9. Any footings at bottom of jamb columns must not interfere with installation of guide rails at floor level.
10. At time of installation, finished floor, free from obstructions, out to a distance of 2 m on each side of door centreline must be available.
11. Header box must be accessible from both sides during installation.


DOOR PROPERTIES:

12. The door is designed to withstand a differential pressure of 1.15kPa x 1.5 FOS.
13. Metal trim: motor side
15. Guide rails, top- and intermediate beams in extruded aluminium with natural finish.
16. Color of header box: BLACK (NCS 9000-N. RAL 9005)
17. Color of door fabric: Color code of door fabric:Grey RAL 7004 (7072/ D3171) (Approved by DIAL)
18. Hand crank for manual operation.

ELECTRICAL:

14. One main control panel provided of PLC type.
15. Audible and visual alarm
16. Safety edge
17. Back-up power switch
18. Approx. size of main control panel: WxHxD (500mm x 600mmx250 mm),
19. Power: 1.4kW
20. Nom. current: 3.3A
21. (max. allowed voltage drop at start: 5%)
22. Power supply required: 3 Phase, 415 V +/-10%, 50 Hz +/- 3%
23. Cable tray size: 50mm (H) x 100mm (W)
24. Conduiting and cabling from motor to control panel is in vendor scope.

BELT HOIST UNITS:
Sk 773.1-90S/4 Z dual brake




KEY PLAN (NOT TO SCALE)

NOTE:
1. 275 MM RCC COLUMN REQUIRED FOR GUIDE MOUNTING.
IF RCC COLUMN NOT AVAILABLE THEN WE WILL REQUIRE MS STRUCTURE FOR THE SAME.


REFERENCE DRAWING :

DIAL-LT-D-UTL-A-20-300 : ARFF4 FIRE STATION ELEVATIONS
DIAL-LT-D-UTL-A-20-301 : ARFF4 FIRE STATION ELEVATIONS
DIAL-LT-D-UTL-A-10-300 : ARFF4 FIRE STATION GROUND FLOOR PLAN


SECTION B-B
Door leaf is not shown for clarification
Scale 1:50




SECTION A-A
Hole pattern for header box attachment
Scale 1:50



Force by differential pressure transferred to guide rail at each intermediate position.
F= 2.7 kN




Load on header box attachment (each screw), due to wind load and door weight



DETAIL B, SCALE (1:5) cross check detail scale

GUIDE RAIL MOUNTING DETAILS



DETAIL A, SCALE (1:10) Cross check detail scale

HEADER BOX MOUNTING DETAILS

L&T Construction
Buildings & Factories

A	APPROVED. PROCEED FOR MANUFACTURE/ CONSTRUCTION.
B	APPROVED WITH COMMENTS. PROCEED TO MANUFACTURE/ CONSTRUCTION SUBJECT TO FULL COMPLIANCE OF ALL COMMENTS AND RESUBMIT THE DOCUMENTS ONLY FOR LEVEL A APPROVAL
C	RESUBMIT AFTER INCORPORATION OF ALL COMMENTS FOR REVIEW.
D	REJECTED. MAKE A RESUBMISSION ALTOGETHER FOR REVIEW.

REVIEW OF THIS DOCUMENT IS ONLY TO CHECK COMPATIBILITY WITH BASIC DESIGN CONCEPT. THIS DOES NOT ABSOLVE THE SUB-CONTRACTOR/ MANUFACTURER FROM HIS RESPONSIBILITY TO MEET THE REQUIREMENT AS PER SPECIFICATIONS, CODES & STANDARDS AND ALL STATUTORY RULES & REGULATIONS, AS EXISTING OR AS MAY BE AMENDED.

CHECKED
LETTER REF :

VERIFIED BY :
DESIGNATION : HEAD ARCHITECT
DATE :
SIGNATURE :

SHOP DRAWING
Building: ARFF4

REVNO.	DESCRIPTION	DESIGNED	DRAWN	CHECKED	APPROVED
C	Revised, issued for approval.	GLP 18.11.2021	GLP 18.11.2021	AK. 18.11.2021	V.T. 18.11.2021
B	Revised, issued for approval.	GLP 15.11.2021	GLP 15.11.2021	AK. 15.11.2021	V.T. 15.11.2021
A	Issued for approval	GLP 30.10.2021	GLP 30.10.2021	AK. 30.10.2021	V.T. 30.10.2021

REVISIONS

CHECKED BY	SIGN	DATE	CHECKED BY	SIGN	DATE	CHECKED BY	SIGN	DATE
ARCHITECTURE			HVAC			GIS		
CIVIL & STRUCTURAL			FPS			GEOTECH.		
ELECTRICAL			PIPING			AIRPORT SYSTEMS		
ELV SYSTEM			PHE			INTERFACE		

DELHI INDIRA GANDHI INTERNATIONAL AIRPORT GAR

L&T Construction

CLIENT : DELHI INTERNATIONAL AIRPORT LIMITED.

PROJECT : NEW MIDFIELD

PROJECT : INDIRA GANDHI INTERNATIONAL AIRPORT PHASE-3A DEVELOPMENT WORKS

PROJECT CONSULTANT: Engineering Design and Research Center L&T Construction (EDRC)

INSTALLED AND SUPPLIED BY: MIAA TECHNOLOGIES PVT LTD

JOB No : JOBNO.	NAME	SIGN	DATE
DSGN	G.L.P		02.10.2021
DRWN	G.L.P		02.10.2021
CHKD	A.K.		02.10.2021
APPD	V.T.		02.10.2021

TITLE: ARFF4 MEGADOOR 5800 X 5400 (RS6)

SCALE 1:50

DRAWING No. DIAL-LT-Q-UTL-A-10-102

PROJECTION THIRD ANGLE


SIZE A3


REV. B C


SHEET


RELEASED FOR ☐ PRELIMINARY ☐ TENDER ☐ INFORMATION ☑ APPROVAL ☐ CONSTRUCTION

Refer general comments given on drawing no A-10-101









NOT INCLUDED IN DOOR SUPPLY:

1. Design and supply of all door supporting structural components.
2. Design and supply of all closure between door and adjacent steel.
3. Door jambs adjustable for overall door width and true to plumb.
4. Paint job after completed door installation.
5. Any frameworks being provided by ASSA ABLOY will be clearly indicated as "by ASSA ABLOY".

REQUIREMENTS ON BUILDING:

6. Door head support must be straight within 1/600 of span in the in/out direction and free from protrusions of any kind.
7. For a single door leaf, door head support should be horizontal and straight within 1/600 of span at distributed full door load.
8. Door side jambs must be smooth, straight and parallel, out of plumb must not exceed 2mm/m (total deviation at full length 5 mm) in any direction.
9. Any footings at bottom of jamb columns must not interfere with installation of guide rails at floor level.
10. At time of installation, finished floor, free from obstructions, out to a distance of 2 m on each side of door centreline must be available.
11. Header box must be accessible from both sides during installation.


DOOR PROPERTIES:

12. The door is designed to withstand a differential pressure of 1.15kPa x 1.5 FOS.
13. Metal trim: motor side
14. Guide rails, top- and intermediate beams in extruded aluminium with natural finish.
16. Color of header box: BLACK (NCS 9000-N. RAL 9005)
17. Color of door fabric: Color code of door fabric: Grey RAL 7004 (7072/ D3171) (Approved by DIAL)
18. Hand crank for manual operation.

ELECTRICAL:

14. One main control panel provided of PLC type.
15. Audible and visual alarm
16. Safety edge
17. Back-up power switch
18. Approx. size of main control panel: WxHxD (500mm x 600mm x 250 mm),
19. Power: 1.4kW
20. Nom. current: 3.3A
21. (max. allowed voltage drop at start: 5%)
22. Power supply required: 3 Phase, 415 V +/-10%, 50 Hz +/- 3%
23. Cable tray size: 50mm (H) x 100mm (W)
24. Conduiting and cabling from motor to control panel is in vendor scope.

BELT HOIST UNITS:
Sk 773.1-90S/4 Z dual brake



KEY PLAN (NOT TO SCALE)

NOTE:
1. 275 MM RCC COLUMN REQUIRED FOR GUIDE MOUNTING.
IF RCC COLUMN NOT AVAILABLE THEN WE WILL REQUIRE MS STRUCTURE FOR THE SAME.

REFERENCE DRAWINGS :

DIAL-LT-D-UTL-A-20-100 : ARFF4 FIRE STATION ELEVATIONS
DIAL-LT-D-UTL-A-20-101 : ARFF4 FIRE STATION ELEVATIONS
DIAL-LT-D-UTL-A-10-100 : ARFF4 FIRE STATION GROUND FLOOR PLAN

SHOP DRAWING
Building: ARFF5

REV.NO.	DESCRIPTION	DESIGNED	DRAWN	CHECKED	APPROVED
C	Revised, issued for approval.	18.11.2021 GJP	18.11.2021 GJP	18.11.2021 AK.	18.11.2021 VT.
B	Revised, issued for approval.	15.11.2021 GJP	15.11.2021 GJP	15.11.2021 AK.	15.11.2021 VT.
A	Issued for approval	30.10.2021 GJP	30.10.2021 GJP	30.10.2021 AK.	30.10.2021 VT.

REVISIONS

CHECKED BY	SIGN	DATE	CHECKED BY	SIGN	DATE	CHECKED BY	SIGN	DATE
ARCHITECTURE			HVAC			GIS		
CIVIL & STRUCTURAL			FPS			GEOTECH.		
ELECTRICAL			PIPING			AIRPORT SYSTEMS		
ELV SYSTEM			PHE			INTERFACE		

L&T Construction
Buildings & Factories

A APPROVED. PROCEED FOR MANUFACTURE/ CONSTRUCTION.
B APPROVED WITH COMMENTS. PROCEED TO MANUFACTURE/ CONSTRUCTION SUBJECT TO THE COMPLIANCE OF ALL COMMENTS AND RESUBMIT THE DOCUMENTS ONLY FOR LEVEL 2 APPROVAL
C RESUBMIT AFTER INCORPORATION OF ALL COMMENTS FOR REVIEW.
D REJECTED. MAKE A RESUBMISSION ALTOGETHER FOR REVIEW.

REVIEW OF THIS DOCUMENT IS ONLY TO CHECK COMPATIBILITY WITH THE DESIGN CONCEPT OF THIS BUILDING. IT DOES NOT RELIEVE THE SUB-CONTRACTOR/ MANUFACTURER FROM HIS RESPONSIBILITY TO MEET THE REQUIREMENTS AS PER SPECIFICATIONS, CODES & STANDARDS, STATUTORY RULES & REGULATIONS, AS EXISTING OR AS MAY BE AMENDED FROM TIME TO TIME.

CHECKED
LETTER REF :
VERIFIED BY
DESIGNATION : HEAD ARCHITECT
DATE :
SIGNATURE :

DELHI INDIRA GANDHI INTERNATIONAL AIRPORT
GMR
L&T Construction

CLIENT : DELHI INTERNATIONAL AIRPORT LIMITED
PROJECT : INDIRA GANDHI INTERNATIONAL AIRPORT PHASE-3A DEVELOPMENT WORKS
CONCEPT :
PROJECT CONSULTANT : Engineering Design and Research Center L&T Construction (EDRC)
INSTALLED AND SUPPLIED BY: IMMA TECHNOLOGIES PVT LTD


JOB No : JOBNO.

	NAME	SIGN	DATE
DSGN	GJP		02.10.2021
DRWN	GJP		02.10.2021
CHKD	AK.		02.10.2021
APPD	V.T.		02.10.2021


TITLE: ARFF5 MEGADOOR 5800 X 5360 (RS6)
SCALE 1:50
DRAWING No. DIAL-LT-Q-UTL-A-10-103
SHEET
PROJECTION FIRST ANGLE
SIZE A3
REV. B

RELEASED FOR ☐ PRELIMINARY ☐ TENDER ☐ INFORMATION ☑ APPROVAL ☐ CONSTRUCTION


C



Interior view, Door closed



SECTION C-C
Open door
Scale 1:50



SECTION C-C
Closed door
Scale 1:50

NOT INCLUDED IN DOOR SUPPLY:

1. Design and supply of all door supporting structural components.
2. Design and supply of all closure between door and adjacent steel.
3. Door jambs adjustable for overall door width and true to plumb.
4. Paint job after completed door installation.
5. Any frameworks being provided by ASSA ABLOY will be clearly indicated as "by ASSA ABLOY".

REQUIREMENTS ON BUILDING:

6. Door head support must be straight within 1/600 of span in the in/out direction and free from protrusions of any kind.
7. For a single door leaf, door head support should be horizontal and straight within 1/600 of span at distributed full door load.
8. Door side jambs must be smooth, straight and parallel, out of plumb must not exceed 2mm/m (total deviation at full length 5 mm) in any direction.
9. Any footings at bottom of jamb columns must not interfere with installation of guide rails at floor level.
10. At time of installation, finished floor, free from obstructions, out to a distance of 2 m on each side of door centreline must be available.
11. Header box must be accessible from both sides during installation.


DOOR PROPERTIES:

12. The door is designed to withstand a differential pressure of 1.15kPa x 1.5 FOS.
13. Guide rails, top- and intermediate beams in extruded aluminium with natural finish.
14. Color of header box: BLACK (NCS 9000-N. RAL 9005)
15. Color of door fabric: Color code of door fabric: Grey RAL 7004 (7072/ D3171) (Approved by DIAL)
16. Metal trim: motor side
17. Hand crank for manual operation.

ELECTRICAL:

18. One main control panel provided of PLC type.
19. Audible and visual alarm
20. Back-up power switch
21. Safety edge
22. Approx. size of main control panel: WxHxD (500mm x 600mmx250 mm),
23. Power: 2.7kW
24. Nom. current: 6.4A
25. (max. allowed voltage drop at start: 5%)
26. Power supply required: 3 Phase, 415 V +/-10%, 50 Hz +/- 3%
27. Cable tray size: 50mm (H) x 100mm (W)
28. Conduiting and cabling from motor to control panel is in vendor scope.

BELT HOIST UNITS:
SK 873.1-100L/4 Z dual brake




KEY PLAN (NOT TO SCALE)


NOTE:
1. 340 MM RCC COLUMN REQUIRED FOR GUIDE MOUNTING.
IF RCC COLUMN NOT AVAILABLE THEN WE WILL REQUIRE MS STRUCTURE FOR THE SAME.

REFERENCE DRAWINGS :


DIAL-LT-D-UTL-A-20-100 : ARFF4 FIRE STATION ELEVATIONS
DIAL-LT-D-UTL-A-20-101 : ARFF4 FIRE STATION ELEVATIONS
DIAL-LT-D-UTL-A-10-100 : ARFF4 FIRE STATION GROUND FLOOR PLAN




SECTION A-A (Scale 1:50)
Hole pattern for header box attachment



SECTION B-B
Door leaf is not shown for clarification
Scale 1:50




DETAIL C, SCALE (1:10)
ANCHOR POSITION FROM COLUMN




change to 1:5


DETAIL B, SCALE (1:10)
GUIDE RAIL MOUNTING DETAILS



DETAIL A, SCALE (1:10)
HEADER BOX MOUNTING DETAILS



Force by differential pressure transferred to guide rail at each intermediate position.
F=4.7 kN



Load on header box attachment (each screw), due to wind load and door weight

L&T Construction
Buildings & Factories

A	APPROVED. PROCEED FOR MANUFACTURE/ CONSTRUCTION.
B	APPROVED WITH COMMENTS. PROCEED TO MANUFACTURE/ CONSTRUCTION SUBJECT TO FULL COMPLIANCE OF ALL COMMENTS AND RESUBMITTHE DOCUMENTS ONLY FOR LEVEL A APPROVAL
C	RESUBMIT AFTER INCORPORATION OF ALL COMMENTS FOR REVIEW.
D	REJECTED. MAKE A RESUBMISSION ALTOGETHER FOR REVIEW.

REVIEW OF THIS DOCUMENT IS ONLY TO CHECK COMPATIBILITY WITH BASIC DESIGN CONCEPT. THIS DOES NOT ABSOLVE THE SUB-CONTRACTOR/ MANUFACTURER FROM HIS RESPONSIBILITY TO MEET THE REQUIREMENT AS PER SPECIFICATIONS, CODES & STANDARDS, ALL APPLICABLE STATUTORY RULES & REGULATIONS, AS EXISTING OR AS MAY BE AMENDED TO DATE OF TENDER.

CHECKED
LETTER REF :

VERIFIED BY : DEBABRATA PAL
DESIGNATION : HEAD ARCHITECT
DATE :
SIGNATURE :

SHOP DRAWING
Building: ARFF5

REV. NO.	DESCRIPTION	DESIGNED	DRAWN	CHECKED	APPROVED
C	Revised, issued for approval.	18.11.2021 G.L.P	18.11.2021 G.L.P	18.11.2021 A.K.	18.11.2021 V.T.
B	Revised, issued for approval.	15.11.2021 G.L.P	15.11.2021 G.L.P	15.11.2021 A.K.	15.11.2021 V.T.
A	Issued for approval	30.10.2021 G.L.P	30.10.2021 G.L.P	30.10.2021 A.K.	30.10.2021 V.T.

REVISIONS

CHECKED BY	SIGN	DATE	CHECKED BY	SIGN	DATE	CHECKED BY	SIGN	DATE
ARCHITECTURE			HVAC			GIS		
CIVIL & STRUCTURAL			FPS			GEOTECH.		
ELECTRICAL			PIPING			AIRPORT SYSTEMS		
ELV SYSTEM			PHE			INTERFACE		

DELHI INDIRA GANDHI INTERNATIONAL AIRPORT GMR

L&T Construction

CLIENT : DELHI INTERNATIONAL AIRPORT LIMITED.
PROJECT: NEW DELHI INTERNATIONAL AIRPORT PHASE-3A DEVELOPMENT WORKS
CONCEPT : ASSA ABLOY
PROJECT CONSULTANT: Engineering Design and Research Center L&T Construction (EDRC)
DETAILED AND SUPPLIED BY: WHA TECHNOLOGIES PVT LTD

JOB No : XXXHO.

	NAME	SIGN	DATE
DSGN	G.L.P		02.10.2021
DRWN	G.L.P		02.10.2021
CHKD	A.K.		02.10.2021
APPD	V.T.		02.10.2021

TITLE: ARFF5 MEGADOOR 8760 X 4988 (RS7)
SCALE 1:50
DRAWING No. DIAL-LT-Q-UTL-A-10-104
SIZE A3
REV. B
PROJECTION FIRST ANGLE
RELEASED FOR ☐ PRELIMINARY ☐ TENDER ☐ INFORMATION ☑ APPROVAL ☐ CONSTRUCTION