Web : www.cosmossystem.in
E-mail : enquiry@cosmossystem.in
Tel. : 0251 - 6560150 / 2620460

COSMOS CONVEYING SYSTEM

NTPL : RG : 1390 21st October, 2021

M/s. NIHVA Technologies Pvt. Ltd.
187, G-Block, Thermax chowk, MIDC
Chinchwad, Pune – 411019.
Mobile : 9168940333
E-mail : procurement@nihva.com

Dear Sir,

Sub.: Offer for Portable Bag Stacker.

This has reference to your comments which you have given for above enquiry. Based on the detail furnished, we are pleased to submit herewith our Offer as per enclosed Annexure.

Our offer mainly consists of the following:

Annexure – I	:	Scope of Supply.
Annexure – II	:	Technical Specifications.
Annexure – III	:	Price Schedule.
Annexure – IV	:	Commercial Terms & Conditions.

We hope the above is in line with your requirement. However, if you require any clarifications / confirmations, please feel free to communicate.

Thanking you,

Very truly yours,

For COSMOS CONVEYING SYSTEM

MANGESH PATGAONKAR

NTPL : RG : 1390 21st October, 2021

ANNEXURE – I

SCOPE OF SUPPLY & SERVICES

Design & Engineering, Manufacturer & Supply of below equipment's.

I] BAG STACKER (2 Nos.)

1. Idlers & Brackets.
2. Pulleys with Bearings and Plummer Blocks.
3. Head & Tail End Structure.
4. Stringer & Support.
5. Skirt Plate.
6. Deck Plate at feed point
7. Tyre Wheels
8. Hydraulic Operated With cylinder
9. Drive Base Frame.
10. Motor, Gearbox, Input & output Coupling
11. Belting.
12. Junction Box

EXCLUSIONS:

1. Any civil works like foundation grouting, leveling, filling etc.
2. Foundation bolts and hold-down bolts.
3. Any other items not mentioned in our technical specification and / or scope of supply.
4. First Fill of Lubricants.
5. Unloading of Material at site and storage thereof.

****

ANNEXURE – II
TECHNICAL SPECIFICATIONS

1. Type of Conveyor :	**Bag High Stacker (Chevron Belt Typ.)**	**Horizontal Bag Mover (Plain Belt Typ.)**
2. C/C Length :	**10 Mtr**	**4 Mtr**
3.Material :	**Bag / Boxes**	**Bag / Boxes**
Weight :	**50 Kg**	**50 Kg**
4. Head & Tail Pulley		
Dia. :	323/273 mm.	323/273 mm.
Width :	700 mm.	700 mm.
Material :	MS.	MS.
5. Belt		
Type :	**315/3 ; Chevron Type**	**315/3 ; Nylon- Nylon**
Width :	**600** mm.	**600** mm.
Rubber Covers :	3/2 mm	3/2 mm
6. Frame :	M. S Fabricated Frame Type**.**	M. S Fabricated Frame Type**.**
7. Tyre Wheels :	Rubber Type wheels Size- ADV 6.00 X 19.	Rubber Type wheels Size- ADV 6.00 X 19.
8. Operation :	HYDRAULIC Operated provided for raising and lowering	HYDRAULIC Operated provided for raising and lowering
9. Boom :	Minimum Delivery Height - 3 Mtr.ec.	Minimum Delivery Height - 3 Mtr.ec.
:	Maximum Delivery Height - 9 Mtr.ec.	Maximum Delivery Height - 9 Mtr.ec.
10. Motor :	T.E.F.C Sq. Cage, 1440 R.P.M., 3 Ph , 1.5HP. standard company make	T.E.F.C Sq. Cage, 1440 R.P.M., 3 Ph , 1.5HP. standard company make
11. Gear box :	Planetary Gear box, reduction, Ratio 120 : 1, NU-5”	Planetary Gear box, reduction, Ratio 120 : 1, NU-5”
12. Take-Up Unit :	Screw Take-Up Typ	Screw Take-Up Typ
13. Speed :	0.2 mtrs/sec	0.2 mtrs/sec
14. Capacity :	Stacking Capacity about 200 to 300 Bags Per hr up to 40 Layers	Stacking Capacity about 200 to 300 Bags Per hr up to 40 Layers

****

ANNEXURE –IV

COMMERCIAL TERMS AND CONDITIONS EQUIPMENT SUPPLY

VALIDITY	**:**	The offer shall be valid for 30 days from date of our offer and thereafter subject to our confirmation.
PRICE	**:**	Prices quoted are Ex.works, Ambernath unpacked. Seaworthy Packing and Forwarding charges shall be extra at the rate of 6% of order value.
PAYMENT	**:**	50% advance along with the PO & 50% against P. I. prior to dispatch.
DELIVERY	**:**	The equipment shall be delivered within 6 to 8 weeks from the date of approval of drawings/advance payment whichever is later.
TAXES	**:**	IGST @ 18 % Extra.
INSPECTION	**:**	Can be carried out at our works by the Purchaser/Purchaser's inspection agency.
DELAYED PAYMENT	**:**	In the event of delay in giving dispatch particulars/taking delivery/making payment by you, we shall charge interest @ 25% per annum extra on the Order value.
ORDER CANCELLATION	**:**	In the event of cancellation of the order we shall be paid on pro-rata basis for the work progressed, and services rendered to the purchaser during the period from issue of order and the date of cancellation of order.
JURISDICTION	**:**	Sales shall be subject to BOMBAY jurisdiction.

****