NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Kotak Mahindra Bank, Thermax chowk,
MIDC, Chinchwad. Pune – 411019

An ISO 9001:2015 Certified Company
GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Date : 13.01.2026
Quote NO : SQA.25.26.0336
Kind Attn : Dr.Pradip Shah
Email Id :
Contact No: 9822043528

Company Name : Dr.Pradip Shah

Project, Location : Ishwarpur, Sangli

Subject : Quotation for Roll Up Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply and Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount
1	**Automatic Roll Up Door**	**1800**	**3440**	**1**	235,000	235,000
2	**Automatic Roll Up Door**	**1430**	**2650**	**1**	225,000	225,000
	Total			**2**		460,000
3	P&F Charges			3%		13,800
	Total Without Taxes					**473,800**
	GST Extra @ 18%			18%		85,284
	Total With Taxes					**559,084**
5	Transportation Charges					Extra at actual
6	Unloading Charges @ Site					In Client Scope

NIHVA TECHNOLOGIES PVT. LTD.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Kotak Mahindra Bank, Thermax chowk,
MIDC, Chinchwad. Pune – 411019

TÜVINDIA
An ISO 9001:2015 Certified Company
GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA Make - Automatic Roll Up Door

Sr. No	Specifications	Description
1	**Product**	Automatic Roll Up Door
1	**Use**	Internal Door
2	**Mounting Location**	Inside of the bay, inside the building
3	**Opening Direction**	Vertical
4	**Opening speed**	upto 1.5 m/s
5	**Opening Speed**	0.5m/Sec. - 1.0m/Sec.
6	**Curtain Material**	PVC Fabric thickness 1.2 mm, 1700 GSM
7	**Guide Material**	2.5 mm thick Aluminum
8	**Stiffeners**	2.5 mm thick Aluminum
9	**Vision Panel**	One row of transparent PVC windows, in rectangular size, assures a good visibility
10	**Fabric Color**	Standard Blue, Grey, Red, Optional with various colors
11	**Roller Shaft**	Tubular pipes
12	**Hood Cover**	1.0 mm thick GI
13	**Motor Cover**	1.0 mm thick GI
14	**Operator & Control**	NIHVA Make Motor
15	**Control Panel**	Push Button operated
16	**Connecting Voltage**	220V , 1Ph , N
17	**Open-Stop-Close Button**	Standarad
18	**Emergency Off Button**	Standard
19	**Emergency Opening**	Crank Handle
20	**Bottom Profile**	PVC profile
21	**Side Brackets**	MS steel brackets with bearings

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Kotak Mahindra Bank, Thermax chowk,
MIDC, Chinchwad. Pune – 411019

An ISO 9001:2015 Certified Company
GST Pune : 27AAECN0437H1ZM

C) General Conditions

1. Installation can start only after site readiness written confirmation and site photo received from client.
2. After site readiness written confirmation, NIHVA Installation team will be mobalised within 4 to 5 days .
3. Installation team will be ideal or required to be demobilize for any reason without completing the work, In that case, min extra charges will be applicable for remobilization of the installation team.
4. NIHVA Supplied products to be installed by NIHVA Team only Or else warranty will not be applicable.
5. Safe storage of material at site until installation, shifting the consignment at the installation location is in client scope.
6. During the period of installation, any shortage of material due to misplace and thieving etc. would be in clients account.
7. During storage at site or warehouse for prolonged periods, if material damaged then repairing/replacement/repainting / refurbishment from the weather deterioration like rust removal will be in client scope.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price	: Ex Works Pune
Delivery	: 6 - 8 weeks from the date of Drawing approval, Firm PO and advance payment receipt
Payment	: 80% Advance along with Confirmed Purchase Order & Balance before dispatch.
Validity	: Validity of Offer is 15 days from the date of quotation
Warranty	: 12 months from the date of supply.
Compensation clause	: In the event if the buyer cancels an order, after the order is confirmed to us, it is binding to the buyer to pay NIHVA a compensation of 25% of order value.
Additional tests or certification	: Any additional tests or certification, which are not within our scope of works but may be required by the Consultant or Client, these will be carried out or provided, subject to the actual requirements but will be at additional cost.
Price clause	: The above Price will increase subject to increase in currency exchange rate which will be as per raw material arrival date at Indian Custom.

Please feel free to Contact for any further Clarification /Information in this Concern.

With Best Regards

Ashwini Jadhav
8530642333
For NIHVA Technologies Pvt Ltd