NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Metec Design & Construction Engineers India Pvt Ltd
1 /460 Multi Industrial Estate
Gerugambakkam Porur Chennai -600122

Date : 11.03.2021
Quote NO : SQT.20.21.3096
Kind Attn : Mari selvam. R,
Email Id : tender@metecdesign.com
Contact No: 9500060762

Project Name & Location: Haier -Ranjangaon

Subject : Quotation for NIHVA Make Dock Leveler

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer -

Sr No	Description	Size		Qty	Ex Work Pune-Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**NIHVA Make Dock Leveler - 10 Ton**	2240	2500	8	225,000	1,800,000	20,000	160,000
				Total		**1,800,000**		**160,000**
				P&F Charges	3%	**54,000**		
				Total Without Taxes		**1,854,000**		**160,000**
				GST Extra @ 18%	18%	333,720		28,800
				Total With Taxes		**2,187,720**		**188,800**
				Transportation Charges		**Extra at actual**		
				Unloading Charges @ Site		**In client scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA Make Dock Leveler - 10 TON





Sr .No.	Specification	Specifications
1	**Capacity**	10 TON
2	**Dock operation mode**	AC power pack hydraulically operated
3	**Lip operation mode**	Hydraulic
4	**Operation control**	Through panel
5	**Loading platform height from road**	1200mm
6	**Travel above & below dock level**	(+) 300 / (-) 250 mm
7	**Platform Size (W x L)**	2240 mm x 2500 mm
8	**Lip size (W x L)**	2240 x 400 mm
9	**Shut Height**	480 mm
10	**Overall length**	2500mm + Lip Length (400mm)
11	**Maximum slope can be achieved**	10%
12	**Clear Pit dimensions (W x L x D)**	(W) 2290mm x (L)2500 mm x (D)485 mm
13	**Hydraulic power pack**	Standard
14	**Driver type**	Direct by electric Motor
15	**Motor Ratings**	1 H.P
16	**Pump design flow**	2.5 LPM
17	**Pump pressure**	120 bar Operating 200 bar Max.
18	**Safety valve set pressure**	120 Kg/cm^2
19	**Pump Type**	Gear
20	**Volume of oil receiver**	7 Lit
21	**No Of Deck cylinder**	2 No
22	**Lip Cylinder**	1 No

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	In client scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In client scope
3	Electrical Supply on the site single phase/three phase points at different places.	In client scope
4	Any civil / masonry/structural work required	In client scope
5	All structure support required	In client scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In client scope
7	Conduits, Cables required	In client scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6-7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 07410169333**

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd