NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

KEC International Ltd. - RPG Group Company
Mumbai

Date : 10.10.2020
Quote NO : SQT/20-21/2753 R
Kind Attn : Mangesh Gursali
Email Id : gursalim@kecrpg.com
Contact No: 9769164384

Subject : Quotation for G I Motorised Rolling Shutter and Automatic Sliding Glass Doors for Tuticorin Airport Project

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**G I Motorised Rolling Shutter**	6400	5500	16	310,000	4,960,000	20,000	320,000
2	**Automatic Sliding Glass Door**	2000	2400	25	175,000	4,375,000	20,000	500,000
	Total			**16**		**9,335,000**		**820,000**
3	P&F Charges			3%		280,050		
	Total Without Taxes					**9,615,050**		**820,000**
	GST Extra @ 18%			18%		1,730,709		147,600
	Total With Taxes					**11,345,759**		**967,600**
3	Transportation Charges					Extra at Actual		
4	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification





Motorized Rolling Shutter

Sr .No.	Specification	G I Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with G I Laths with thickness of 1 mm.
2	**Mounting Location area**	Outside area
3	**Mounting Surface**	On Concrete /Steel
4	**Curtain Panel**	The panel made of 1.0mm thick MS.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of MS Sheet Thickness 0.9 mm
12	**Surface finish**	Powder Coating
13	**Perforation Slat**	1000mm Perforation Slat at 3000mm height from Bottom.
13	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

Automatic Sliding Glass Door

Sr .No.	Specification	
1	**Operator Type**	Bi part operator.
2	**User Modes**	Auto, Open, In,Out, Locked, Partial opening
3	**Operator Dimension**	125 x 168 mm
4	**Installer Settings**	Opening speed, Closing Speed,Hold Open Time, Half Opening distance, Opening, Direction, Installer Password, User Password
5	**Obstacle Detection**	Permanent obstacle detection in both opening and closing cycles
6	**Surface Treatment:**	Silver Anodized
7	**Safety**	3D infrared curtain Photocell, Radar, opening radar with integrated curtain photocell, Energy saving EN16006
8	**Glass**	12 mm Toughened Glass
9	**Interlocking**	Two doors can be operated using interlocking mode
10	**Compatibility**	Compatibilty with Fire alarm and access control system
11	**Energy Saving**	Short braking distance during opening and closing cycle for Energy saving
12	**Fault Monitoring**	Error codes are shown on the digital position selector screen
13	**Class of Protection**	**IP 22**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	
3	Electrical Supply on the site single phase/three phase points at different places.	
4	Any civil / masonry/structural work required	
5	All structure support required	
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	
7	Conduits, Cables required	

D) Terms & Conditions

Price : Extra at Actual

Delivery : 5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd