# PURCHASE ORDER

## ARP CONSTRUCTION & INFRASTRUCTURE

Shop No 105, 1st floor, H-wing Jay Ganesh Samrajya Spine Road Bhosari 411039.
Email:arp.infrastructure@gmail.com Mob:9850015082,9970089098

**To,**
**NIHVA Technologies Pvt. Ltd.**
**187, G-Block, 1st Floor, Above Renault Showroom,**
**Thermax chowk, MIDC, Chinchwad. Pune – 411019**
**GST TIN NO: 27AAECN0437H1ZM**

**Delivery Address:**
**John Deere India Private Limited**
**Gat No.166-167 & 271-291**
**Sanaswadi Pune 412208**
**GST TIN NO : 27AAACJ4233B1Z4**

**PURCHASE ORDER**

**GST TIN NO: 27AAOFA1574D1ZJ**
**PAN NO :AAOFA1574D**
**Date: 19-05-2021**
**P.O.NO: ARP5M005**

| Sr | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width | Clear Length | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **Motorized Single Skin Rolling** | 3700 | 4000 | 1 | 1,14,000 | 1,14,000 | 12,500 | 12,500 |
| 2 | **Motorized Single Skin Rolling** | 4000 | 4000 | 4 | 1,24,000 | 4,96,000 | 12,500 | 50,000 |
| 3 | **Motorized Single Skin Rolling** | 4000 | 5000 | 3 | 1,42,000 | 4,26,000 | 12,500 | 37,500 |
| | | | | Total | | **10,36,000** | | **1,00,000** |
| 4 | | | P&F Charges | 3% | | **31,080** | | |
| | | | Total Without Taxes | | | **10,67,080** | | **1,00,000** |
| | | | GST Extra @ 18% | 18% | | 1,92,074 | | 18,000 |
| | | | **Total With Taxes** | | | **12,59,154** | | **1,18,000** |

**B) Technical Specification**

**Motorized Rolling Shutter**

| Sr .No. | Specification | GI Motorized Rolling Shutter |
|---|---|---|
| 1 | **Description:** | Motorised Rolling Shutter with GI Slats with thickness of 1 mm. |
| 2 | **Mounting Location** | Inside area / Outside area |
| 3 | **Mounting Surface** | Side Brackets: Optional = On Concrete /Steel & Side |
| 4 | **Curtain Panel** | The panel made of 1.0mm thick GI. |
| 5 | **Curtain panel size** | 75mm wide |
| 6 | **Curtain Profile** | Curved |
| 7 | **Bottom Profile** | M. S. Plate 100 mm x 2.5 mm thick with angle stiffener |
| 8 | **Side Guide Profile** | M.S." T" Shaped profile 65 mm -150 mm x 3 mm thick. |
| 9 | **Roller Shaft** | M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día - |
| 10 | **Side Brackets** | MS Plate 3 mm to 10 mm thick, as per the opening dimension. |
| 11 | **Hood Cover** | Made of GI Sheet Thickness 0.9 mm GF mm |
| 12 | **Surface finish** | Powder coated |
| 13 | **Drive Unit & Mounting** | Electric Motor - Indirect Mounting - Sprocket chain arrangement – |
| 14 | **Cycle per Day** | 50 Cycles per Day. |

**TERMS AND CONDITIONS:**

**1)Transportation Charges In NIHVA Scope**

**2)Delivery: 1)Total work completed date of shed 2 & 3 will be 25/05/2021**
**2) Shed 1 work completed date will be 05/06/2021.**

**3)Payment: 1)500000/- Five lakh Advance.**
**2)450000/- Four lakh fifty thousand against proforma invoice.**
**3)117080/- Seventy six thousand nine hundred ten After material delivery within 3 days**
**4)100000/- One lakh of installation will be after compilation & inspection by client within 7 days.**

**4)Warranty: 12 months from the date of Installation**

**For**
**ARP CONSTRUCTION & INFRASTRUCTURE**

**Authorised Signature**