Sales Quote

An ISO 9001:2008 Certified Company

Quote No: SQT.18-19.1651 **Date: 05/22/2019**

Manjushree Technopack Ltd.

Unit 2, 60 E & F, Bommasandra Industrial Area,
Near Karnataka Bank, Jigani Road
Bengaluru -
Karnataka -India

Kind Attention: Mr. Ramesh

Phone:- (947) 400-7290
Email ID: 99ramesh.d@gmail.com

Project Name And Location :

Subject : Quote for - Scissor Lift

Dear Sir,

Thank you for your opportunity and trust shown on “NIHVA.” your preferred partner for innovative solutions.This has reference to your above mentioned requirement as well as our subsequent communication. Please find below our best offer.

Commercial Offer :-

Sl.No.	Description	Price	Qty	Unit	Total
1.	Scissor Lift Option 1 - Manually Operated Capacity : 400 kgs Platform Size : (L) 1500 mm x (W) 900 mm Shut height : 500 mm Max height : 2000 mm Lift height : 1600 mm Hand pump operated Railing on both length side : 900 mm height Wheel : Dia 150 x 50 (Swivel & fixed nylon type) (Supply + Installation)	₹ 146,250.00	1	Nos	₹ 146,250.00
2.	Scissor Lift Option - 2 Automatically Operated Capacity : 400 kgs Platform Size : (L) 1500 mm x (W) 900 mm Shut height : 500 mm Max height : 2000 mm Lift height : 1600 mm Power pack : 1 HP, 3 PH Railing on both length side : 900 mm height Wheel : Dia 150 x 50 (Swivel & fixed nylon type) (Supply + Installation)	₹ 222,500.00	1	Nos	₹ 222,500.00

Sub Total	₹ 368,750.00
Grand Total	**₹ 368,750.00**

Sales Quote

An ISO 9001:2008 Certified Company

Quote No: SQT.18-19.1651					Date: 05/22/2019
Sl.No.	**Description**	**Price**	**Qty**	**Unit**	**Total**
GST Pune	27AAECN0437H1ZM				

General Pre requisite at site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places
3 Provide electrical cables near to the installation machinery
4 Fork lift/crane to be provided if required
5 Scaffolding require for Installation it is in client scope

Limit of Supply

1 Provide place to store the material to be installed
2 Be responsible for the safe custody of all material
3 Provide place to safely store all the tools of installation
4 Provide change & rest room for the workers

Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
2 In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account
3 Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel

Client Scope

1 Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2 Any civil / masonry/structural work required to support are in client scope
3 All structure support is in client scope
4 NIHVA Will provided structure drawing only if required
5 Existing/Repair/ Modification/ Refurbishment charges will be extra

Terms & Conditions

1 **Price** : Ex works Pune
2 **P & F Charges**: @3% of Total Supply Value
3 **Freight Notes**: Extra as applicable
4 **Payment**: 80% Advance along with confirm purchase order & Balance 20% before dispatch
5 **Taxes**: GST @ 18%
6 **Validity**: Validity of Offer is 15 days from the date of quotation.
7 **Warranty**: 12 months from the date of supply
8 **Delivery** : 5-6 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval
9 **Insurance :**Extra As applicable

Please feel free to Contact **Mr. Arjun Patil on (855) 109-6333** for any further Clarification /Information in this Concern.

Sales Quote

An ISO 9001:2008 Certified Company

Quote No: SQT.18-19.1651 **Date: 05/22/2019**

With Best Regards

Smita Khare
+91-9637991333
For Nihva Technologies Pvt Ltd