NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Ashok Constructions
Office: B-601, Sukhwani Glory
Dapodi, Pune - 411012
Maharashtra, India

Date : 04.10.2019
Quote NO : SQT.19.20.2084R2
Kind Attn : Mr. S C Gujrathi
Email Id : ashokpilgonde@gmail.com
Contact No: 9970012907

Project Name & Location:

Subject : Quotation for Sliding Gate & Boom Barrier

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Motorised Single Leaf Sliding Gate	6000	1800	2	2,52,000	5,04,000	15,000	30,000
2	Motorised Two sided Two Leaf Telescopic Sliding Gate	18000	1800	1	10,78,000	10,78,000	20,000	20,000
3	Wicket Gate	1200	1800	2	30,000	60,000	5,000	10,000
4	Automatic Boom Barrier	6000		4	1,30,000	5,20,000	15,000	60,000
		Total Value (considered Option 2A to calculate the Total value)				**21,62,000**		**1,20,000**
5		**P&F Charges**		0%		-		
		Total Without Taxes				**21,62,000**		**1,20,000**
		GST Extra @ 18%		18%		3,89,160		21,600
		Total With Taxes				**25,51,160**		**1,41,600**
6		Transportation Charges				**included**		
7		Unloading Charges @ Site				**included**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) Technical Specifications

Sr. No	Description	Specifications	
1	**Door type**	**Motorised Sliding Gate**	**Telescopic Sliding Gate**
2	**Clear Opening gate dimension**	(W) 6000 mm X (H) 1800 mm	(W) 18000 mm X (H) 1800 mm
3	**Opening Direction**	Horizontal - from left to right or reverse	Horizontal - from left to right or reverse
4	**Mounting Location area**	Inside area	Inside area
5	**Design Pattern**	Standard Tubular Design Pattern	Standard Tubular Design Pattern
6	**Outer Frame Tube Sizes**	80 x 80 x 3.2 mm	80 x 80 x 3.2 mm
7	**Internal Vertical Tube Sizes**	40 x 40 x 2.6 mm	40 x 40 x 2.6 mm
8	**Gap Between Tubes**	125 mm C/C	125 mm C/C
8	**Perforation Sheet**	2 mm thick sheet	2 mm thick sheet
9	**Bottom Rail on ground**	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
10	**Bottom Rollers**	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
11	**Full Height Column sizes**	80 x 80 x 3.2 mm	80 x 80 x 3.2 mm
12	**Guide Rollers supporter during Gate movement**	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
13	**Painting**	Two Coats of Primer and Two Coats of Synthetic Enamel Paint	Two Coats of Primer and Two Coats of Synthetic Enamel Paint
14	**Safety**	Flashing Light, Safety Photocell	Flashing Light, Safety Photocell
14	**Motor**	100% Imported from Europe	100% Imported from Europe
14	**Telescopic Mechanism**	NA	Gate with Telescopic Mechanism

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	NIHVA Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope
8	Lifting Equipements	NIHVA Scope

D) Terms & Conditions

Price : At Site_John Deere Pune

Delivery : 3 -4 weeks from confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Arjun Patil on 8551096333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd