NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Suroj Buildcon Pvt. Ltd.
Pune

Date : 05.10.2019
Quote NO : SQT.19.20.2140
Kind Attn : Mr. Nikhil Bakane
Email Id : nbakane@suroj.com
Contact No: **020 4135 5926**

Project Name & Location: CAF, Bhiwadi II, Rajasthan

Subject : Quotation for Rolling Shutter, Sliding Gate, Boom Barrier & Dock leveler

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2 & 3
C.	General Conditions	4
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	MS Motorised Rolling Shutter	6000	7000	1	3,34,000	3,34,000	20,000	20,000
2	MS Motorised Rolling Shutter	5500	7000	1	3,17,000	3,17,000	20,000	20,000
3	MS Motorised Rolling Shutter	3000	3000	1	99,000	99,000	20,000	20,000
4	MS Motorised Rolling Shutter	5000	7000	1	2,72,000	2,72,000	20,000	20,000
5	MS Motorised Rolling Shutter	4500	5500	1	1,90,000	1,90,000	20,000	20,000
6	MS Motorised Rolling Shutter (With & Without grill)	2000	3000	1	95,000	95,000	20,000	20,000
7	Motorised Sliding Gate	10000	1800	1	4,58,000	4,58,000	20,000	20,000
8	Dock Leveler	3000	3000	1	2,25,000	2,25,000	20,000	20,000
9	Boom Barrier	6000	-	1	1,30,000	1,30,000	12,000	12,000
				Total		**21,20,000**		**1,72,000**
10	P & F Charges			3%		**63,600**	-	-
	Total Without Taxes					**21,83,600**		**1,72,000**
	GST Extra @ 18%			18%		3,93,048		30,960
	Total With Taxes					**25,76,648**		**2,02,960**
11	Transportation Charges					**In Client Scope**		
12	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

MS Rolling Shutter		
Sr .No.	**Specification**	**Motorized Rolling Shutter**
1	Description:	Motorised Rolling Shutter with MS Laths with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete /Steel & Side
4	Curtain Panel	The panel made of 1.0mm thick MS.
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	Hood Cover	Made of MS Sheet Thickness 0.9 mm GF mm with 25x25x3mm angle stiffener
12	Surface finish	PU paint or Powder coated
13	Drive Unit & Mounting Type	Indirect Drive, Electric Motor - Direct Mounting - Sprocket chain arrangement – IP54 Protection
14	Grill	For 1 Mtr height

Sliding Gate		
Sr. No	**Description**	**Specifications**
1	Door type	Motorised Single Leaf Sliding Gate
2	Clear Opening gate dimension	(W) 10000 mm X (H) 1800 mm
3	Opening Direction	Horizontal - from left to right or reverse
4	Mounting Location area	Inside area
5	Design Pattern	Standard Tubular Design Pattern
6	Outer Frame Tube Sizes	50 x 50 x 4.5 mm
7	Internal Vertical Tube Sizes	25 x 25 x 3.2 mm
8	Gap Between Tubes	100 mm C/C
9	Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
10	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
11	Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
12	Painting	Powder Coating
13	Metal Rack	Zinc plated metal rack
14	Installation Checks	need to be check = space requirements + substructure + Mounting access

Dock Leveler

Sr. No	Description	Specifications
1	Capacity	9Ton
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Through panel
5	Loading platform height from road	1250mm
6	Travel above & below dock level	(+) 300 / (-) 250 mm
7	Platform Size (W x L)	3000 mm x 3000 mm
8	Lip size (W x L)	3000 x 400 mm
9	Shut Height	480 mm
10	Overall length	3000mm x 3000mm + Lip Length (400mm)
11	Maximum slope can be achieved	10%
12	Clear Pit dimensions (W x L x D)	(W) 3050mm x (L) 3050 mm x (D)485 mm
13	Hydraulic power pack	Standard
14	Driver type	Direct by electric Motor
15	Motor Ratings	1 H.P
16	Pump design flow	2.5 LPM
17	Pump pressure	120 bar Operating 200 bar Max.
18	Safety valve set pressure	120 Kg/cm²
19	Pump Type	Gear
20	Volume of oil receiver	7 Lit
21	No Of Deck cylinder	2 No
22	Lip Cylinder	1 No
23	Dock Bumper	Pair of Dock Bumper

Boom Barrier

MICHELANGELO BT A Barrier-1No.(Opening Time- 6S)
• Round Boom First part-1No.
• Round Boom Second part- 1 No.
• Anchor Base- 1No.
• MOB. Boom Rest-1No.
• Rubber Safety Profile- 1No.
• OMEGA AT Acce. - 1No.
• Transmitter with Channels- 1No.
• Push Button
• Frequency of use- Continuous
• Motor Power Supply- 24V

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 7 - 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain on 8551092333**

With Best Regards
Vivek
8530370333
For NIHVA Technologies Pvt Ltd