NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

# Sales Quotation

**Quotation No. SQT/18-19/1421R1** **Date : 4-Apr-19**

**REWARD CONSTRUCTIONS PVT. LTD.**
768/1, Flat No - 2
"Prabhi" Opp. P.Y.C. Gymkhana.
Pune - 411 004.

**Kind Attn :** Mr. Manish Nikam
**Email :** mk.nikam@rewardconstructions.com
**Contact No :** 7389034619

**Project Name And Location : ZF India Pvt. Ltd.**

**Subject : Revised Quotation for Boom Barrier, Motorised Rolling Shutter, Sliding and Wicket gate and High Speed Door and Sliding Door.**

Dear Sir

Thank you for the opportunity and trust shown on "NIHVA", your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

**Commercial Offer**

| Sr. No | Description | Qty Sq m | Unit | Rate / Sq M in INR | Net Amount INR |
|---|---|---|---|---|---|
| A | **BOOM Barrier ( MICHELANGELO60 BT A U Made in Italy – 100% Imported)**<br>**Each Boom Barrier Set include:**<br>**MICHELANGELO BT A Barrier-1No.**<br>**• Round Boom First part-1No.**<br>**• Round Boom Second part- 1 No.**<br>**• Anchor Base- 1No.**<br>**• MOB. Boom Rest-1No.**<br>**• Rubber Safety Profile- 1No.**<br>**• OMEGA AT Acce. - 1No.**<br>**• Transmitter with Channels- 1No.**<br>**(Supply + Installation)** | | | | |
| 1 | **Size- 6 Mtr MICHELANGELO60 BT A U** | 1 | Nos. | 1,63,000 | 1,63,000 |
| | | | | | |
| B | **Motorized Rolling Shutter**<br>**MS Slat:1mm (Width less than 3.5M) and 1.2mm (Width more than 3.5M)Thk, Curved Type Profile with heavy duty Shaft, Guide, Indirect Drive Motor, Hood Cover with Painting**<br>**( Supply + Installation )** | | | | |
| 1 | Size : (W) 4000 mm X (H) 4000 mm | 1 | Nos. | 1,47,000 | 1,47,000 |
| 2 | Size : (W) 3000 mm X (H) 3000 mm | 1 | Nos. | 1,06,000 | 1,06,000 |
| | | | | | |
| C | **Gear Operated Rolling Shutter**<br>**MS Slat:1mm (Width less than 3.5M) and 1.2mm (Width more than 3.5M)Thk, Curved Type Profile with heavy duty Shaft, Guide, Indirect Drive Motor, Hood Cover with Painting**<br>**( Supply + Installation )** | | | | |
| 1 | Size : (W) 4000 mm X (H) 4000 mm | 1 | Nos. | 1,37,000 | 1,37,000 |
| 2 | Size : (W) 3000 mm X (H) 3000 mm | 1 | Nos. | 96,000 | 96,000 |

| | | | | | |
|---|---|---|---|---|---|
| D | **Motorised Rolling Shutter with Grill**<br>**MS Slat:1mm (Width less than 3.5M) and 1.2mm (Width more than 3.5M)Thk, Curved Type Profile with heavy duty Shaft, Guide, Indirect Drive Motor, Hood Cover with Painting**<br>**( Supply + Installation )** | | | | |
| 1 | Size : (W) 4000 mm X (H) 4000 mm | 1 | Nos. | 1,55,000 | 1,55,000 |
| 2 | Size : (W) 3000 mm X (H) 3000 mm | 1 | Nos. | 1,11,000 | 1,11,000 |
| | | | | | |
| **E** | **Albany Make Rapid Roll Up Door RR300+AL**<br>**(100% Imported with all components – made in Germany)** | | | | |
| Door panel: | Transparent PVC with Red (RAL 3002) reinforcement stripes. | | | | |
| Barrel: | Aluminium, anodized with shafts made of galvanized steel | | | | |
| Wind Reinforcement: | Door Panel wind tabs for improved wind resistance | | | | |
| Side Frames: | Aluminium profiles, anodised | | | | |
| Drive Unit: | Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door) | | | | |
| Self-opening: | Standard - the door can be opened partially up to 1,8 m by releasing the brake manually. | | | | |
| Bottom beam: | Anodized extruded aluminium. | | | | |
| Control system: | MCC Vector Control - frequency converter control system for a dynamic, smooth door movement, located close to the drive unit Max. Opening Speed 2.2m/s Max. Closing Speed 0.9 m/s | | | | |
| Safety features: | Safety edge, safety photocell (Transmitter/Receiver) inside side columns | | | | |
| 1 | **Size: 4000 mm X 4500 mm**<br>**( Supply + Installation )** | 1 | No | 6,89,000 | **6,89,000** |
| | | | | | |
| **F** | **ASSA ABLOY-BESAM-Automatic Sliding Door SL 500**<br>**100% imported from Sweden**<br>**Specifications :**<br>**1. Main power supply**<br>**2. Operator type- Bi part operator.**<br>**3. User interface- Auto Partial/Auto/one way/closed including LED status**<br>**4. Battery- Battery 12 V power fail open**<br>**5. open Operator lock- Electric lock ( fail safe)**<br>**6. Glass : 10mm thick toughened glass** | | | | |
| 1 | Size: (W) 1100 mm x (H) 2400 mm<br>**( Supply + Installation )** | 2 | No | 2,10,000 | 4,20,000 |

| | | | | | |
|---|---|---|---|---|---|
| G | **Double Leaf Motorized Sliding Gate**<br>**• Outer Tube - 80 x 80 x 3.2mm MS SQ. TUBE**<br>**• Inner Tube - 40 x 40 x 2mm MS SQ. TUBE**<br>**• Gap - 125 mm**<br>**( Supply + Installation )** | | | | |
| 1 | Size : (W) 18000 mm X (H) 1500 mm | 1 | Nos. | 13,44,000 | 13,44,000 |
| | | | | | |
| H | **Manual Wicket Gate**<br>**( Supply + Installation )** | | | | |
| 1 | Size : (W) 1000 mm X (H) 2500 mm | 1 | Nos. | 44,000 | 44,000 |
| | | | | | |

| | | |
|---|---|---|
| **GST Pune** | | 27AAECN0437H1ZM |

**General Prerequisites Required at Site**

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

**Limit of Supply**

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

**Quote/Supply is based on**

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

**The supply included only those mentioned in the quote & does not include**

1. Unloading from truck placement on site
2. Electrical connection for control panel.

**Client Scope**

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

**Terms and Conditions :**

| | | | |
|---|---|---|---|
| 1 | **Price** | : | Ex. Works Pune |
| 2 | **P & F Charges** | : | @3% of total supply value |
| 3 | **Freight Notes** | : | Extra as applicable + Taxes |
| 4 | **Delivery** | : | 10-11 weeks for High Speed Door and 5-6 weeks for others from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval. |
| 5 | **Payment** | : | 80% Advance along with Confirmed Purchase Order & Balance before dispatch. |
| 6 | **Insurance** | : | Extra As applicable |
| 7 | **Tax** | : | GST extra @ 18% |
| 8 | **Validity** | : | Validity of Offer is 15 days from the of quotation |
| 9 | **Warranty** | : | 12 months from the date of supply. |

Please feel free to Contact **Mr. Bhavin Jain** on **08551092333** For any further Clarification /Information in this Concern.

With Best Regards

Swapnil Kulat

7219207333

For NIHVA Technologies Pvt Ltd