NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Ariam door controls
Hyderabad

Date : 08.01.2021
Quote NO : SQT.20.21.2936
Kind Attn : Mr. Chandrasekhar
Email Id : chandrasekhar@adchyd.biz
Contact No: 9866800025

Project Name & Location: Hyderabad

Subject : Quotation for Fire Rated Motorised Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Fire Rated Motorised Rolling Shutter**	6500	5700	1	525,000	525,000	20,000	20,000
				Total Value		**525,000**		**20,000**
				P&F Charges	3%	15,750		
				Total Without Taxes		**540,750**		**20,000**
				GST Extra @ 18%	18%	97,335		3,600
				Total With Taxes		**638,085**		**23,600**
				Total (Supply + Installtion) with Taxes				**661,685**
4	Transportation Charges					**Extra at Actual**		
5	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) Technical Specifications





2 Hrs. Fire Rated Rolling Shutters - 100% IMPORTED

- **Shutter Slats: Zinc coated steel solid slats**
- **Slat Thickness: 1.0mm thick**
- **Shutter Guide: Galvanize Steel, 3mm thick**
- **Operated by: Motor with one unit push button switch & manual override**

Fire Rated Rolling Shutter

Sr .No.	Specification	Fire Rated Rolling Shutter
1	**Shutter Curtain**	Single Skin Design
2	**Guide Rail**	Powder coated
3	**Bottom Bar**	Powder coated
4	**Type of Mounting**	Standard
5	**Motor Drive Unit**	Motorise 230Volt 1P 50Hz with Manual override chain
6	**Standard RAL colors:**	RAL 9002
7	**MAKE & Model**	SKB Make - 2 HRS Fire Rated Shutters BS476
8	**Standard**	BS 476
9	**Fire Rating**	2 Hrs.
10	**Roller Curtain**	Zinc Coated Steel Solid Slats - 1mm thick
11	**Bottom Rail**	Powder coated
12	**Side Guide & Angles**	Galvanise Steel G65, 3mm thick
13	**Shaft/Barrel**	Shaft
14	**Hood & Motor Cover**	0.9mm thick GI
15	**Operation**	Motorise 230Volt 1P 50Hz with Manual override chain
16	**Auto Closing Mechanism**	Fire Shutter will auto close via 71 C degrees Thermal Fusible Link
17	**Power Consumption**	0.75 Kw
18	**Control Switch**	one unit push button switch
19	**Accessories**	Manual override chain
20	**Cable Length**	6 Mtr
21	**Finish/ Colour**	Powder Coated - RAL 9010 (White) or RAL - 7025 - Grey
22	**Protection Category**	BS 476

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	
3	Electrical Supply on the site single phase/three phase points at different places.	
4	Any civil / masonry/structural work required	
5	All structure support required	
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	
7	Conduits, Cables required	

D) Terms & Conditions

Price : Ex Price Pune

Delivery : 9-10 weeks from the date of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% advance along with purchase order & balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of Installation.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bikash Sahu 8530926333.**

With Best Regards
Smita Khare
9673991333
For NIHVA Technologies Pvt Ltd