NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

SCON Projects Pvt. Ltd
Office No.1A, Harshal Corner, Plot No.5, Survey
No.78, Left Bhusari Colony, Paud Rd., Kothrud
Pune - 411038 .

Date : 30.06.2020
Quote NO : SQT/19-20/2477R1
Kind Attn : Mr. Kamlesh Bhagade
Email Id : kamleshb@sconprojects.com
Contact No: 8308809561

Subject : Quotation for Sectional Door (Project Location - Innovatec india pvt. Ltd.).

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Scetional Door - Horizontal Mounting	3500	2500	2	2,65,000	5,30,000	10,000	20,000
2	Scetional Door - Horizontal Mounting (Low Lift)	2500	3000	1	2,55,000	2,55,000	10,000	10,000
				Total		**7,85,000**		**30,000**
3	P&F Charges			0%		-		
	Total Without Taxes					7,85,000		30,000
	GST Extra @ 18%			18%		1,41,300.00		5,400
	Total With Taxes					**9,26,300**		**35,400**
4	Transportation Charges					Included		
5	Unloading Charges @ Site					In NIHVA Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) **TECHNICAL SPECIFICATION -**

Sr .No.	Specification	Sectional Door -Crawford - NIHVA Assaabloy	
1	Door type	1042P	
2	Door produced Based on which certificatio	Doors produced according to ISO 9000 or ISO 14000 certified processes	
3	Opening/Closing Speed	0.25 m/s	
4	Door Material	GI Steel with PUF inside	
5	Panel Thickness	42mm	
6	Panel colour	RAL 9002 Powder coated	
7	External surface of the panel	diamond grid design with a glossy finish at the section joints.	
8	inside surface of the panel	Monolithic surface on the inside of the door	
9	Broken cold bridge	Section joints with broken cold bridges	
10	Door sealent	All door sealants made of EPDM rubber.	
11	All Panel height	All panels should be 545mm high	
12	Panel Inside insulation metrial	Insulation material to be CFC free polyuretane foam.	
13	Panel Flame Retardent standrad	Flame retardant polyurethane foam according DIN4102-class B2.	
14	Steel component Material	All steel components to be electro galvanized	
15	Hinge Material	Glass fibre reinforced Polyamide	
16	Panel Thickness	42 mm	
17	Spring Material surface finish	Powder coated	
18	Water Penetration	EN 12425	class 3
19	Air Permealibity	EN12426	class 2
20	Wind Load	EN21424	class 3
21	Thermal Transittance	EN 12428 1.10W /m2K	
22	Bottom sealing	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber	
23	Door saftey device 1	Doors equiped with spring break device	
24	Door saftey device 2	Door equiped with pneumatic safety edge	
25	Door saftey 3	Having hinges flush with the inside door surface is a safety feature that eliminates the risk of things or people getting caught by parts protuding	
26	Incase of Power failuer	One can operate the Door manually	
27	Operator power conumption	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W	
28	Drive Unit & Mounting Type	Single phase 230V direct drive on shaft	
29	Emergency Operation	by Disengagement rope manual	
30	Operating Switch	Up/Down Keypad + stopbutton	
31	Environmental Green Product Declaration Certification	as per ISO 14025 and EN 15804	

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 12 -13 weeks for Sectional Doors from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd