NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

RIECO Industries Ltd.
Pune

Date : 07.05.2022
Quote NO : **MHE_22.23.0006**
Kind Attn : Mr. Bharat Jadhav
Email Id : bharat.jadhav@rieco.com
Contact No: 9545194899

Project Name & Location: RIECO Industries Ltd., Pune

Subject : Quotation for Take Up Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr. No.	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Take Up Conveyor** Total length: 2.9 mtr	1	3,10,000	3,10,000	30,000	30,000
		Total		3,10,000		30,000
2	GST Extra @ 18%	18%	Extra At Actual			
3	P&F Charges @ 3%	3%	Extra At Actual			
4	Transportation Charges		Extra At Actual			
5	Insurance		Extra At Actual			
6	Unloading Charges @ Site		In Client Scope			

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sr. No.	Parameters	Specification
1	Product Type	Sugar & Cocoa Powder Bags
2	Product Weight	25 Kg
3	Capacity	60-90 Bags per Hour
4	Loading/Unloading	Manual
5	Belt Width	600 mm
6	InclinationAngle	25°
7	Contact Parts	SS 304
8	Non Contact Parts	SS 304
9	Gear Motor	Bonfiglioli
10	Bottom & Top paltform- NIHVA scope	

C) General Conditions

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 After 1 year warranty, Non comprehensive AMC will be provided by NIHVA which is at an additional cost.

Note: Please find below List which are in Client Scope.

Sr. No	
1	Secured and fully covered Store area to keep the material.
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required.
5	All structure support required.
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8-9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 60% Advance along with Confirmed Purchase Order.
35% Along with Approval of Drawing and before start a Production.
5% Against completion of Installation, Testing and Commissioning.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd