Sales Quotation

Quotation No - SQT/19-20/1749 **Date : 08.07.2019**

Progressive infra project pvt. Ltd.
2nd Floor, Sai Niketan,
S. No.31/ 1A/2-C, Opp. Mega Mart
Old Pune -Mumbai Highway ,
Dapodi, Pune- 411012

Kind Attn: Mr. Sumeet Patil
Email ID: purchase@pipil.co.in
Contact No: 7875337746

Project Name And Location : Intorq India Pvt Ltd Pune.

Subject : Quotation for Motorized Rolling Shutter, Dock Leveler & Scissor Lift

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Motorized Rolling Shutter** **Technical Specifications:** **• MS Slat : 1 mm Thick** **• Profile : Curved Type Profile with heavy duty Shaft** **• Hood Cover & Motor Cover : 0.9 mm Thick GI material** **• Gear Assembly** **• With Painting** **(Supply + Installation)**				
1	Size (W) 3000 mm x (H) 3400 mm (Indirect Drive)	1	No	103,600	103,600
2	Size (W) 3000 mm x (H) 3400 mm (Direct Drive)	2	No	160,060	320,120
B	**Dock Leveler (NIHVA Make)** **2 cylinder for Deck & 1 cylinder for LIP Operator by Standard Control Panel (Deck Up / Down / Lip Up / Down) Rubber Bumpers.**				
1	**Dock Levelers Capacity 6 Ton Point Load & 15 Ton UDL** Size : (W) 2000mm X (L) 2500 mm (Supply + Installation)	2	No	255,000	510,000
C	**Scissor Lift**				
	Capacity : 5 ton				
	Platform size : 3000L x 2700W				
	Shut ht : 600 mm				
	Max ht : 1800 mm				
	Lift ht : 1200 mm				
	Power pack : 5HP, 3PH				
	Railing : 900 mm ht both length sides only (3000L)				
	Color : as per req.				
1	Option 1 **Hydraulic Scissor Lift with manual Lip Operation** Supply + Installation	1	No	685,690	685,690
2	Option 2 **Hydraulic Scissor Lift with Hydraulic Lip Operation** Supply + Installation	1	No	782,770	782,770

GST Pune	**27AAECN0437H1ZM**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex works Pune
2	**P & F Charges**	:	@ 3% of Total supply value
3	**Freight Notes**	:	Extra as applicable
4	**Delivery**	:	5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with confirm purchase order & Balance 20% before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST Extra 18%
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact Mr. Ravindra Kharat on 7410169333 for any further Clarification /Information in this Concern.

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd