Date - 03.12.2025

Project : Elysian , Goregaon East
Package : Retractable Roof Works
Title : Annexure 02 Bill of Quantities (BOQ) : Addendum 01

Sr. No	Description	Unit	Qty	Rate	Amount
I	**Design, Supply, Installation, Testing and Commissioning(DSITC) of Automatic Retractable Roof (L Shaped Enclosure) including but not limited to following** **1. Design & Engineering** • Structural and architectural design as per approved drawings. • Design to accommodate the following unfactored loads: - Self-weight - Live Load: 1.5 kN/m² - Wind Load: 4 kN/m² • Submission of complete design documentation including: - Structural calculations - Material specifications - Load assessments - Connection details • Third-party structural stability certificate from an independent qualified consultant. • Compliance with relevant codes, standards, and statutory requirements. • No fabrication or installation to commence without Employer's written approval of design and certification. **2. Material & System Specifications** • Roofing Sheet: Polycarbonate Compact Clear/Embossed, 3.0 mm thick • Frame: Powder Coated Aluminium Profile (RAL Shade 9006) • Guide System: Anodized Aluminium Guide • Interlocking Mechanism: Integrated for weather-tight sealing • Motorized Operation: - Motor type : Vendor to specify - Speed: 09–12 m/min - Power: As per roof dimensions - Mechanical limit switch - Rack and pinion arrangement - Control panel with 2 remote controls • Sealing: EPDM gaskets and sealants • Drainage: Built-in provision for water management 3. Installation & Commissioning • Complete installation, alignment, testing, and commissioning of the retractable roof system. • Submission of operation manuals, warranty certificates, and as-built drawings. 4. Defect Notification Period (DNP) Maintenance • Comprehensive maintenance during Defect Notification Period as specified in Appendix, including the below mentioned at no additional cost: - Preventive and corrective maintenance - Replacement of defective parts - Emergency breakdown response • Minimum 4 scheduled site visits per year by qualified technical personnel. • Submission of maintenance logs and service reports after each visit. 5. Special Warranties (Effective from date of acceptance by Employer): • Aluminium Profile: 10 years • Polycarbonate Sheet: 10 years • Powder Coating: 10 years		**2**	**27,00,000**	**54,00,000**
	Clear Opening Size (Plan Area) : 3400 mm X 2000 mm				
1	Tower A	NOS	1		0
2	Tower B	NOS	1		0
3	Tower C	NOS	1		0
4	Tower D	NOS	1		0
	Sub Total (Without GST)				**54,00,000**
	GST				9,72,000
	Total Amount (With GST)				**63,72,000**

Sr. No	Description	Unit	Qty	Rate	Amount
II	**Non Comprehensive AMC Charges** Scope of Non-Comprehensive MaintenanceIncludes routine inspection, servicing, and breakdown support. Spare parts and major repairs are chargeable separately. Minimum 4 scheduled visits per year. Service reports to be submitted after each visit.				
1	First Year after DLP	Yearly	1		94000
2	Second Year after DLP	Yearly	1		101050
3	Third Year after DLP	Yearly	1		108629
4	Fourth Year after DLP	Yearly	1		116776
	Sub Total (Without GST)				**4,20,455**
	GST				75,682
	Total Amount (With GST)				**4,96,137**

Payment : 50% Advance along with Confirmed Purchase Order, 40% Before dispatch & 10% After installation.

Sr. No	Description	Unit	Qty	Rate	Amount
III	**Spare part list (during Non Comprehensive AMC Period) : Vendor to Specify**				
1					
2					
3					
4					
	Sub Total (Without GST)				-
	GST				-

	Total Amount (With GST)				-