WORK ORDER

NIHVA TECHNOLOGIES PVT. LTD.

Client:	
Finearc Systems Pvt Ltd	
Address:	
S. No. 21, F-2 Block, M.I.D.C, Pimpri, Pune - 411018	

PO Number:	PO No.202100855 R1	**W. O. No-**	SO/21-22/0106
PO Dated :	29-10-2021	**W. O. Date**	08-11-2021
PO Received Date:	08-11-2021	**Sales Co ordinator**	Shailesh
Ref. Quotation:	SQA.21.22.0275R	**Front Sales Person**	VT

Dispatch Address:

S. No. 21, F-2 Block, M.I.D.C, Pimpri, Pune - 411018

A Technical Terms:

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Supply Rate	Installation Rate	Total Amount	Dwg. Approval Status
1	Machine Protection Doors without anti UV Window (W)1800 mm X (H)2000 mm	Door version : Vertical Rapid Roller Door for machine protection. Side Frames : Aluminum anodized two parts, to have easy access to switches and service. Door blade : Rolltex Plus Curtain Bottom beam : Aluminium anodized. Drive unit : Drive unit IP 55, Motor LH, with control cable (standard length = height of door) Opening / closing speed : Approx. max. 2,4 / 1,7 m/s Control system : MCC Vector Control Power suppy : 3/(N)/PE 230/380/400/415 V, 50 Hz bottom edge with pre running photocells . Safety limit switch : 1 Schmersal safety limit switch PL e EN ISO 13849-1, SIL 3 EN 62061 on drive side integrated in the side frame to save space. Motor & Hood Cover: Included Motor LHS Grey Colour - RAL 7001	Nos	1		0	0	Pending
						Total	0	

Non standard items/extra requirement, if any:	

B Commerical Terms:

1	Payment Terms:	30% Advance and 30 Days PDC for Balance amount Delivery.		
2A	Delivery Date as per PO:	On or Before 25.12.2021	2B. Required Delivery Date:	
3A	Transportation Scope:	CLIENT	3B. Transportation Charges:	
4	P&F Charges:	NIL		
5A	Loading Scope:	CLIENT	5B. Loading Charges:	
6A	Unloading Scope:	CLIENT	6B. Unloading Charges:	
7A	Lifting Equipments Scope:	CLIENT	7B. Available Lifting Equipments:	
8	Warranty:	12 months from the date of supply.		
9A	Height arrangement Scope:	CLIENT	9B. Available Equipments for working at Site:	
10	Electricity Supply:	CLIENT		
11	GST:	As Applicable		
12A	Installation Scope:		12B. Installation required date:	
13	Mode of import:	Sea		
14	HSS:	Yes		
15	Documentation Required:	High Sea Sale documents		
16A	Total site visits required:		16B. Site visit charges:	

Certified that the above work order finalised in presence of:

AGM	SALES		Operation	PROJECT	DESIGN	Date & Time
A.K.	V.T.		S.B.	S.M.	G.P	08-11-2021