**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

# NIHVA Sales Quotation

**Vijay Rajan Lubricants,**
New Mumbai.

**Date : 10.02.2021**
Quote NO : SQT.20.21.3012
**Kind Attn : Ms. Sultani**
Email Id : vijayrajanmumbai@gmail.com
Contact No: 7304099585

**Project Name & Location:** Gear operated Rolling Shutter, New Mumbai

**Subject : Quotation for MS Rolling Shutter**

**Dear Sir,**

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |

**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Length (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **Gear Operated Rolling Shutter** | 4572 | 3962 | 15 | 1,13,000 | 16,95,000 | 20,000 | 3,00,000 |
| | | | | **Total** | | **16,95,000** | | **3,00,000** |
| 2 | | | P&F Charges | 3% | | **50,850** | | |
| | | | **Total Without Taxes** | | | **17,45,850** | | **3,00,000** |
| | | | GST Extra @ 18% | 18% | | 3,14,253 | | 54,000 |
| | | | **Total With Taxes** | | | **20,60,103** | | **3,54,000** |
| 3 | | | Transportation Charges | | | | | **Client Scope** |
| 4 | | | Unloading Charges @ Site | | | | | **Client Scope** |

NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**Gear Operated Rolling Shutter**

| Sr .No. | Specification | MS Gear Operated Rolling Shutter |
|---|---|---|
| 1 | **Description** | Gear Operated Rolling Shutter with MS slats with thickness of 1 mm. |
| 2 | **Mounting Location area** | Inside area / Outside area |
| 3 | **Mounting Surface** | Side Brackets: Optional = On Concrete |
| 4 | **Curtain Panel** | The panel made of 1.0mm thick MS. |
| 5 | **Curtain panel size** | 75mm wide |
| 6 | **Curtain Profile** | Curved |
| 7 | **Bottom Profile** | M. S. Plate 100 mm x 2.5 mm thick with angle stiffener |
| 8 | **Side Guide Profile** | M.S." T" Shaped profile 65 mm -150 mm x 3 mm thick. |
| 9 | **Roller Shaft** | M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h |
| 10 | **Hood Cover** | Made of GI Sheet Thickness 0.9 mm GF mm |
| 11 | **Surface finish** | 2 Coats (each coat of 35 microns DFT) of EPOXY polyamide-based enamel finish of approved color and make over a Coat (each one coat 25 microns DFT) of EPOXY polyamide based red oxide zinc phosphate primer |
| 12 | **Operation** | Gear Assembly. |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 4-5 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% along with confirmed purchase order & Balance before dispatch

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333**

**With Best Regards**
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd