WORK ORDER

Client
Lupin Limited

PO Number:	3400135982	**W. O. no-**	SO/20-21/073
PO Dated :	23/12/2020	**W. O. Date**	26/12/2020
PO Received Date:	24/12/2020	**Sales Co ordinator**	Shailesh Bhoir
Ref. Quotation:	SQT.20.21.2809R5	**Front Sales Person**	Shrikant Mirkute

Dispatch Address:

Lupin Limited, Biotech - Pune, Gat No - 1156, village : - Ghotawade, Tal - Mulshi, Pune - 412115

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Rate	Amount	Installation	Total
1	Single Skin Motorized Rolling Shutter with Honeycomb Grill Size : 2500 mm X 3000 mm	Size : 2500 mm X 3000 mm, Description: Motorised Rolling Shutter with GI Slats with thickness of 1 mm., Mounting Location area: Inside area / Outside area, Mounting Surface Side Brackets: Optional = On Concrete /Steel & Side, Curtain Panel : The panel made of 1.0mm thick GI., Curtain panel size : 75mm wide, Curtain Profile : Curved with 1000mm Honeycomb Grill to be installed at eyelevel height, Bottom Profile : M. S. Plate 100 mm x 2.5 mm thick with angle stiffener, Side Guide Profile : M.S." U" Shaped profile., Roller Shaft : M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h, Side Brackets : MS Plate 3 mm to 10 mm thick, as per the opening dimension., Hood Cover : Made of GI Sheet Thickness 0.9 mm GF mm, Surface finish : Powder coated - Finish with two coats of Polyurethane spray paint similar to RAL9006, Drive Unit & Mounting Type : Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection, Control Panel : Three Station Push Button with Deadman Control, Safety : Safety Catch.	No.	2				
2	Motorized Rolling Shutter Size : 3950 mm X 3200 mm	Size : 3950 mm X 3200 mm, Description: Motorised Rolling Shutter with GI Slats with thickness of 1 mm., Mounting Location area: Inside area / Outside area, Mounting Surface Side Brackets: Optional = On Concrete /Steel & Side, Curtain Panel : The panel made of 1.0mm thick GI., Curtain panel size : 75mm wide, Curtain Profile : Curved with 1000mm Honeycomb Grill to be installed at eyelevel height, Bottom Profile : M. S. Plate 100 mm x 2.5 mm thick with angle stiffener, Side Guide Profile : M.S." U" Shaped profile., Roller Shaft : M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h, Side Brackets : MS Plate 3 mm to 10 mm thick, as per the opening dimension., Hood Cover : Made of GI Sheet Thickness 0.9 mm GF mm, Surface finish : Powder coated - Finish with two coats of Polyurethane spray paint similar to RAL9006, Drive Unit & Mounting Type : Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection, Control Panel : Three Station Push Button with Deadman Control, Safety : Safety Catch.	No.	2				
3	Motorized Rolling Shutter Size : 4650 mm X 4000 mm	Size : 4650 mm X 4000 mm, Description: Motorised Rolling Shutter with GI Slats with thickness of 1 mm., Mounting Location area: Inside area / Outside area, Mounting Surface Side Brackets: Optional = On Concrete /Steel & Side, Curtain Panel : The panel made of 1.0mm thick GI., Curtain panel size : 75mm wide, Curtain Profile : Curved with 1000mm Honeycomb Grill to be installed at eyelevel height, Bottom Profile : M. S. Plate 100 mm x 2.5 mm thick with angle stiffener, Side Guide Profile : M.S." U" Shaped profile., Roller Shaft : M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h, Side Brackets : MS Plate 3 mm to 10 mm thick, as per the opening dimension., Hood Cover : Made of GI Sheet Thickness 0.9 mm GF mm, Surface finish : Powder coated - Finish with two coats of Polyurethane spray paint similar to RAL9006, Drive Unit & Mounting Type : Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection, Control Panel : Three Station Push Button with Deadman Control, Safety : Safety Catch.	No.	1				
4	Motorized Rolling Shutter Size : 5300 mm X 4000 mm	Size : 5300 mm X 4000 mm, Description: Motorised Rolling Shutter with GI Slats with thickness of 1 mm., Mounting Location area: Inside area / Outside area, Mounting Surface Side Brackets: Optional = On Concrete /Steel & Side, Curtain Panel : The panel made of 1.0mm thick GI., Curtain panel size : 75mm wide, Curtain Profile : Curved with 1000mm Honeycomb Grill to be installed at eyelevel height, Bottom Profile : M. S. Plate 100 mm x 2.5 mm thick with angle stiffener, Side Guide Profile : M.S." U" Shaped profile., Roller Shaft : M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h, Side Brackets : MS Plate 3 mm to 10 mm thick, as per the opening dimension., Hood Cover : Made of GI Sheet Thickness 0.9 mm GF mm, Surface finish : Powder coated - Finish with two coats of Polyurethane spray paint similar to RAL9006, Drive Unit & Mounting Type : Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection, Control Panel : Three Station Push Button with Deadman Control, Safety : Safety Catch.	No.	1				
				6		-		-

A) Commerical Terms

1)	**Payment Terms:**	30% Advance, 60% against Proforma, 10% after installation., Sr. No. 1 to 4 : 30% Advance (Basic), 60% against proforma invoice (Cheque will be released against dispatch details and final invoice), 10% after completion of installation and commissioning. Sr. No. 5 : 100% after completion of work.
2)	**Delivery Date as per PO:**	Within 3 Weeks from the date of Purchase Order/LOI conditions for Dispatch : Material should be despatched only after receiving our despatch clearance, wherever applicable Lupin will prepare design qualification (DQ), perform factory acceptance test (FAT) and then will give despatch clearance.
3)	**Transportation:**	Inclusive
4)	**P&F Charges:**	Nil
5)	**Loading:**	In NIHVA Scope
6)	**Unloading:**	Client Scope
7)	**Lifting Equipments:**	Client Scope
8)	**Warranty:**	12 months from the date of supply
9)	**Height arrangement:**	Client Scope
10)	**Electricity Supply:**	Client Scope
11)	**GST:**	Extra@18%
12)	**Installation Scope:**	In NIHVA Scope
13)	**Mode of import:**	NA
14)	**HSS:**	NA
15)	**Documentation Required:**	Standard Handover Documents

Certified that the above work order finalised in presence of:

AGM	SALES	PROJECT	PPC	DESIGN	Date & Time
A. K.	V.T.				