WORK ORDER

NIHVA TECHNOLOGIES PVT. LTD.

Client:	
Alfa Laval India Private Limited	
Address:	
Mumbai-Pune Road, Dapodi, - 411 012 Pune - India	

PO Number:	1254203	**W. O. No-**	SO/22-23/057
PO Dated :	11.10.22	**W. O. Date**	15-11-2022
PO Received Date:	14-11-2022	**Sales Co ordinator**	Shailesh
Ref. Quotation:	SQA.22.23.0019R3	**Front Sales Person**	Shailesh

Dispatch Address:

Alfa Laval India Private Limited
Mumbai-Pune Road, Dapodi, - 411 012 Pune - India

A **Technical Terms:**

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Supply Rate	Installation Rate	Total Amount	Dwg. Approval Status
1	Turnstile	Full height Single lane Turnstile of in Stainless Steel Frame Structure and Top Cabinet for Housing Electronics and Mechanical Head Assembly, Stainless Steel 3x120 Degree Rotor including canopy, Single Lane 304 stainless steel, Passage width: ≤550mm. per lane. Power Supply AC220, 50 Hz. Operating voltage motor 24V	No	1		0	0	Pending
2	Manual Single Leaf Wicket Gate W1570 X H 2310mm	Door type - Manual Single Leaf Wicket Gate Mounting Location area - Inside area Design Pattern - Standard Tubular Design Pattern Outer Frame Tube Sizes- 72X72X3.2mm MS SQ. TUBE Internal Vertical Tube Sizes - 32X32X2.6mm MS SQ. TUBE Gap Between Tubes- 125 mm C/C Painting -QD Paint & QD Primer Operation - Manually Opening	No	1		0	0	Pending
						Total	0	

Non standard items/extra requirement, if any:	

B	**Commerical Terms:**			
1	**Payment Terms:**	90% AGAINST DELIVERY & 10% AGAINST INSTALLATION & COMMISIONING WORK		
2A	**Delivery Date as per PO:**	7 - 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.	**2B. Required Delivery Date:**	
3A	**Transportation Scope:**	NIHVA Scope	**3B. Transportation Charges:**	
4	**P&F Charges:**	NIL		
5A	**Loading Scope:**	NIHVA Scope	**5B. Loading Charges:**	
6A	**Unloading Scope:**	NIHVA Scope	**6B. Unloading Charges:**	
7A	**Lifting Equipments Scope:**	NIHVA Scope	**7B. Available Lifting Equipments:**	
8	**Warranty:**	36 months from the date of supply.		
9A	**Height arrangement Scope:**	CLIENT Scope	**9B. Available Equipments for working at Site:**	
10	**Electricity Supply:**	CLIENT Scope		
11	**GST:**	18%		
12A	**Installation Scope:**	NIHVA Scope	**12B. Installation required date:**	
13	**Mode of import:**	NA		
14	**HSS:**	NA		
15	**Documentation Required:**	Standard Handover Documents		
16A	**Total site visits required:**		**16B. Site visit charges:**	

Certified that the above work order finalised in presence of:

GM	AGM	SALES		Operation	PROJECT	DESIGN	Date & Time
Mr. Ameet Kurhade		Mr. Shailesh		Mr. Kiran M	Mr. Sandeep M	Ms. Sujata Biradar	24-11-2022