Sales Quotation

Quotation No - SQT/18-19/0045R **Date : 15-04-2019**

AAR Indamer Technics Pvt. Ltd
Plot No 2A-2B-2C, MIHAN SEZ, Khapri
Nagpur – 441108, Maharashtra, India

Kind Attn : **Mr.Rohan Dhumal**
Email : rohand@aarindamertechnics.com
Contact No : 95796 22491

Project Name & Location :

Subject : Supply of Fire Rated and Non Fire Rated Rolling Shutter

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr. No.	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**2 Hr. Fire Rated Rolling Shutter (100% Imported)** **Shutter Slats:** Zinc coated steel solid slats**, Slat Thickness:** 1.0mm thick**, Shutter Guide:** Galvanize Steel, 3mm thick**, Operated by:** Motorize with one unit push button switch & manual override				
1	Size : (W) 2800 mm x (H) 2900 mm	6	No	280,000	1,680,000
2	Installation Charges for Fire Rated Rolling Shutter	6	No	20,000	120,000
				Total	**1,800,000**
B	**Motorised Non Fire Rated Rolling Shutter** GI Slat: 1 mm Thk, Curved Type Profile with heavy duty Shaft, Guide, Hood Cover - 0.9mm, Motor - Indirect Drive with painting				
1	Size : (W) 2800 mm x (H) 2900 mm	2	No	84,000	168,000
2	Installation Charges for Rolling Shutter	2	No	20,000	40,000
				Total	**208,000**
				Grand Total	**2,008,000**

General Prerequisites Required at Site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places.
3 Provide electrical cables near to the installation machinery
4 Scaffolding require for Installation it is in client scope.

Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
2 In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to
3 Billing will be as per the supply of material ,not as per site measurements

Client Scope

1 Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2 Any civil / masonry/structural work required to support are in client scope
3 All structure support is in client scope
4 NIHVA Will provided structure drawing only if required
5 Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	At Site
2	**P & F Charges**	:	NIL
3	**Freight Notes**	:	Included
4	**Delivery**	:	8-9 weeks for Fire Rated Rolling Shutter and 4 -5 weeks for Non Fire Rated Rolling Shutter from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST @18%
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Vijay Tarak on 8551093333** For any further Clarification / Information in this Concern.

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd