WORK ORDER

Client:	
PARC Robotic Systems Pvt.Ltd	
Address:	
Phase 4, Plot No. PAP-A-9/2, Chakan Industrial Area, NIGHOJE,Taluka Khed, Pune Pune MH 410501	

PO Number:	22PO0010678	**W. O. No-**	SO/22-23/077
PO Dated :	3/3/2023	**W. O. Date**	3/6/2023
PO Received Date:	3/6/2023	**Sales Co ordinator**	Shailesh Bhoir
Ref. Quotation:	SQA.22.23.0369R2	**Front Sales Person**	

Dispatch Address:

Phase 4, Plot No. PAP-A-9/2, Chakan Industrial Area,
NIGHOJE,Taluka Khed, Pune Pune MH 410501

A Technical Terms:

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Supply Rate	Installation Rate	Total Amount	Dwg. Approval Status
1	ASSA ABLOY Machine Protection Door RP300 (W) 2000 mm X (H) 2000 mm	Sheet 2	Nos	1		0	-	Pending
2	ASSA ABLOY Machine Protection Door RP300 (W) 2000 mm X (H) 2200 mm	Sheet 2	Nos	1		0	-	Pending
						Total		-

Non standard items/extra requirement, if any:	**NOTES : 1. Please Mention our Part No & PO No on Delivery Challan and Invoice. 2. All material to be sent with Material Test Certificate, Self Inspection Reports. 3. Refer Latest drawings as applicable 4. Material should be send with Invoice(2 copies) & Delivery Challan.**

B Commerical Terms:

1	Payment Terms:	20% Advance+70 % Along with Taxes At The Time of Dispatch+10 % Before Commissioning At PARC/Customer		
2A	Delivery Date as per PO:	8 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.	2B. Required Delivery Date:	
3A	Transportation Scope:	In Client Scope	3B. Transportation Charges:	
4	P&F Charges:	NIL		
5A	Loading Scope:	In NIHVA Scope	5B. Loading Charges:	
6A	Unloading Scope:	In Client Scope	6B. Unloading Charges:	
7A	Lifting Equipments Scope:	In Client Scope	7B. Available Lifting Equipments:	
8	Warranty:	12 Months from date of Supply		
9A	Height arrangement Scope:	In Client Scope	9B. Available Equipments for working at Site:	
10	Electricity Supply:	In Client Scope		
11	GST:	18%		
12A	Installation Scope:	In Client Scope	12B. Installation required date:	
13	Mode of import:	NA		
14	HSS:	NA		
15	Documentation Required:	Standard Handover Documents		
16A	Total site visits required:		16B. Site visit charges:	

Certified that the above work order finalised in presence of:

GM	AGM	SALES		Operation	PROJECT	DESIGN	Date & Time
Mr. Ameet Kurhade		Mr. Shailesh Bhoir		Mr. Kiran M	Mr. Sandeep	20/03/2023	

Sr .No.	Specification	Albany make Machine Protection Door RP300
1	**Door version:**	Vertical Rapid Roller Door for machine protection.
2	**Side Frames:**	Aluminum anodized two parts, to have easy access to switches and service.
3	**Door blade:**	Curtain RollTex Original (silicone-free) without window, according to the following RAL colours blue (5002) orange (2009) or grey (7001).
4	**Bottom beam**	Aluminium anodized.
5	**Drive unit:**	Drive unit IP 55, RH as an option, with control cable (standard length = height of door)
6	**Opening / closing speed:**	Approx. max. 2,0 / 1,2 m/s
7	**Control system:**	MCC Frequency converterVector Control for opening/closing speed up to 2,4 / 1,4 m/s for door with safety contact edge, protection IP 55. Without display, interface card delivered separately, including power- and interface cable, with main switch in separate box.
8	**Power suppy:**	3L(N)PE 380/400/415/440/460 and 480 V, 50/60 Hz
9	**Safety features:**	Safety edge with cable chain integrated in side frames, door line photocell (Transmitter / Receiver) inside side frames, emergency crank and mechanical drop-down protection.
10	**Safety limit switch:**	1 Schmersal safety limit switch PL e EN ISO 13849-1, SIL 3 EN 62061 on drive side integrated in the side frame to save space.
11	**Display**	Display "Up-Stop-Down"
12	**Interface Card**	MCC without display unit, with combibox in plastic (175x250x150 mm) with interface card and main switch included in combibox, including power- and interface cable.
13	**Accessories**	Top Cover, Motor Cover on RHS