**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2008 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

# NIHVA Sales Quotation

**Suroj Buildcon Pvt Ltd**
Pune

**Date : 16.10.2019**
Quote NO : SQT.19.20.1729R
**Kind Attn :** Mr. Prashant Raut
Email Id : praut@suroj.in
Contact No: 777 401 4847

**Project Name & Location:** MANE INDIA DAHEJ

**Subject : Quotation for High Speed Door**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.**


| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |


**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Length (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **HIGH SPEED PVC ROLL UP DOOR** | 2700 | 3100 | 6 | 326,000 | 1,956,000 | 18,000 | 108,000 |
| 2 | **HIGH SPEED PVC ROLL UP DOOR** | 2200 | 3100 | 25 | 318,000 | 7,950,000 | 18,000 | 450,000 |
| 3 | **HIGH SPEED PVC ROLL UP DOOR** | 3000 | 3100 | 6 | 332,000 | 1,992,000 | 18,000 | 108,000 |
| 4 | **HIGH SPEED PVC ROLL UP DOOR** | 1400 | 3100 | 2 | 290,000 | 580,000 | 18,000 | 36,000 |
| | | | | | Total | 12,478,000 | | 702,000 |
| | P&F Charges | | | 3% | | **374,340** | | |
| | **Total Without Taxes** | | | | | **12,852,340** | | **702,000** |
| | GST Extra @ 18% | | | 18% | | 2,313,421 | | 126,360 |
| | **Total With Taxes** | | | | | **15,165,761** | | **828,360** |
| | Transportation Charges | | | | | **In Client Scope** | | |
| | Unloading Charges @ Site | | | | | **In Client Scope** | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2008 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**HIGH SPEED PVC ROLL UP DOOR**



- Safe & for continous operations
- Self Supporting Construction with anti crash protection system for bottom profile
- Smooth & silent opening & closing
- Can be equipped with full vision PVC curtain
- Modular Interchaegable panels permit to replace worn & damged panels

| Sr. No | Description | Specifications |
|---|---|---|
| 1 | Use | Internal Door |
| 2 | Speed | Inverter Motion system to adjust different speeds, with progressive control of acceleration & deceleration during braking |
| 3 | Opening speed | 3 m/s |
| 4 | Closing speed | 0.8 m/s |
| 5 | Control Panel | 4 Push Button operated |
| 6 | Security Features | EN 13241-1 Standard |
| 8 | Resistance to wind load | EN12424 upto class 2 |
| 9 | curtain | Fabric Transparent PVC section |
| 10 | Guide Material | Stainless Steel |
| 11 | Operator & Control | |
| 11.1 | Connecting Voltage | 220V , 1Ph , N |
| 11.2 | Open-Stop-Close Button | Standarad |
| 11.3 | Protection Category | IP 54 / IP 65 |
| 11.4 | Power Consumption | 0.75 kw Motor |
| 11.5 | Emergency Off Button | Standard |
| 11.6 | Closing Zone Monitoring | Optical Safety edge |
| 11.7 | External Route Monitoring | Photocell |
| 11.8 | Emergency Opening | Crank Handle |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2008 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

| | |
|---|---|
| **Price** | : Ex Works Pune |
| **Delivery** | : 6 - 7 weeks for Dock Leveler & Rolling Shutter, 11-12 Weeks for Sectional Door from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval. |
| **Payment** | : 80% Advance along with Confirmed Purchase Order & Balance before dispatch. |
| **Validity** | : Validity of Offer is 15 days from the date of quotation |
| **Warranty** | : 12 months from the date of supply. |

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain on 8551092333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd